THE AHMEDABAD DISTRICT CO-OPERATIVE BANK LTD.					
SCHEDULE-B					
PART-A CIVIL WORKS					
NAME OF WORK- CIVIL WORKS AT- NEW OFFICE BUILDING, AHMEDABAD					
NO	**ITEMS**	**QTY**	**UNIT**	**RATE RS.**	**TOTAL RS.**
	PLASTIC PAINT				
	PREPERING SURFACE BY SAND PAPER PROVIDING & APPLAYING WALL PUTTY BEFORE WALL PAINTING THREE COATS WITH PLASTIC EMULSION PAINT OF APPROVED BRAND AND MANUFACTURE ON UNDER COATED WALL SURFACE TO GIVEN AN EVEN SHADE INCLUDING THOROUGHLY BRUSHING THE SURFACE FREE FROM MORTAR DROPPINGS AND OTHER FOREIGN MATTER AND SAND PAPERED SMOOTH ETC. COMP.				
1	**GROUND FLOOR**	**900.00**	**SFT**	**32.00**	**28,800.00**
2	**FIRST FLOOR**	**900.00**	**SFT**	**32.00**	**28,800.00**
3	**SECOND FLOOR**	**900.00**	**SFT**	**32.00**	**28,800.00**
4	**THIRD FLOOR**	**900.00**	**SFT**	**32.00**	**28,800.00**
5	**FOURTH FLOOR**	**900.00**	**SFT**	**32.00**	**28,800.00**
6	**FIFTH FLOOR**	**900.00**	**SFT**	**32.00**	**28,800.00**
7	**SIXTH FLOOR**	**900.00**	**SFT**	**32.00**	**28,800.00**
	FLASE CEILING GYPSUM				
	PROVIDING & FIXING CEILING OF GYP BOARD 12.5 MM TH. INCLUDING 25MM LONG SCREW,SUSPENDED GI CHANNELS,ALL JOINTS SHALL BE FINISHED WITH JOINT PAPER USING JOINTING COMPOUND ETC COMP.				
8	**GROUND FLOOR**	**900.00**	**SFT**	**98.00**	**88,200.00**
9	**FIRST FLOOR**	**900.00**	**SFT**	**98.00**	**88,200.00**
10	**SECOND FLOOR**	**900.00**	**SFT**	**98.00**	**88,200.00**
11	**THIRD FLOOR**	**900.00**	**SFT**	**98.00**	**88,200.00**
12	**FOURTH FLOOR**	**900.00**	**SFT**	**98.00**	**88,200.00**
13	**FIFTH FLOOR**	**900.00**	**SFT**	**98.00**	**88,200.00**
14	**SIXTH FLOOR**	**900.00**	**SFT**	**98.00**	**88,200.00**
	FLASE CEILING GYPSUM PATTA				
	PROVIDING & FIXING CEILING PATTA OF GYP BOARD 12.5 MM TH. INCLUDING 25MM LONG SCREW,SUSPENDED GI CHANNELS,ALL JOINTS SHALL BE FINISHED WITH JOINT PAPER USING JOINTING COMPOUND ETC COMP.				
15	**GROUND FLOOR**	**100.00**	**SFT**	**90.00**	**9,000.00**
16	**FIRST FLOOR**	**100.00**	**SFT**	**90.00**	**9,000.00**
17	**SECOND FLOOR**	**100.00**	**SFT**	**90.00**	**9,000.00**
18	**THIRD FLOOR**	**100.00**	**SFT**	**90.00**	**9,000.00**
19	**FOURTH FLOOR**	**100.00**	**SFT**	**90.00**	**9,000.00**

20	**FIFTH FLOOR**	**100.00**	**SFT**	**90.00**	**9,000.00**
21	**SIXTH FLOOR**	**100.00**	**SFT**	**90.00**	**9,000.00**
	PART-A CIVIL WORK TOTAL RS.				**8,82,000.00**

Signature and Stamp of Bidder

THE AHMEDABAD DISTRICT CO-OPERATIVE BANK LTD.					
SCHEDULE-B					
PART-B FURNITURE WORKS					
NAME OF WORK- FURNITURE WORKS AT- NEW OFFICE BUILDING, AHMEDABAD					
NO	**ITEMS**	**QTY**	**UNIT**	**RATE RS.**	**TOTAL RS.**
	GROUND FLOOR				
1	**SLIDING DOOR**	**1**	**NOS.**	**60,000**	**60,000.00**
	PROVIDING AND FIXING SIZE OF DOOR 1200X2450(H) POLISHED VENEER ON BOTH SIDE AND ALUMINUM SECTION FRAMING INSIDE,EBCO SLIDING CHANNEL IS USED, WHICH WILL BE FITTED ON THE UPPER SIDE OF DOOR.				
2	**FULLY GLASS DOOR**	**90.00**	**SFT**	**875.00**	**78,750.00**
	PROVIDING & FIXING 12MM TH.TOUGHENED GLASS DOOR WITH S.S HANDLE, LOCK,HINGES,PATCH INCLUDING MAKING HOLE & OPENING ETC.COMP				
3	**FLOOR SPRING**	**3.00**	**NOS**	**10,500.00**	**31,500.00**
	PROVIDING & FIXING DOOR FLOOR SPRING SET OF APPROVED QUALITY INCLUDING CUTTING MAKING SOLT AT TOP & BOTTOM & MAKING GOOD OF FLOORING & TOP SURFACE ETC.COMP OF OZONE MANUFACTURER.				
4	**12 MM TOUGHENED FULLY GLASS PARTITION**	**145.00**	**SFT**	**650.00**	**94,250.00**
	PROVIDING & FIXING 12MM TH. TOUGHENED GLASS WITH S.S STUD & BRACKET INCLUDING MAKING NECESSARY HOLE & OPENING ETC.COMP				
	FIRST FLOOR				
5	**CHAIRMAN'S TABLE**	**1.00**	**NOS.**	**1,55,000.00**	**1,55,000.00**
	PROVIDING & FIXING TABLE SIZE OF 2400MMX 800MMX750MM(H),TABLE TOP IN MICHEAL ANGELO MARBLE (**ABOUT RS.950/- PER SFT),** PLY BODY WITH PU FINISHED ,ALUMINUM POWDER COATED GRILL IN FRONT & FOOTREST BELOW.				
6	**SIDE TABLE**	**1.00**	**NOS.**	**60,000.00**	**60,000.00**
	PROVIDING & FIXING TABLE SIZE OF 1200MMX450MMX610MM(H) ,TABLE TOP IN MICHEAL ANGELO MARBLE,PU FINISHED DRAWER & SHUTTERS MADE FROM 18MM THICK PLY WITH MAGNET,MULTIPLE DRAWERS, LOCKS AND TELESCOPIC CHANNEL FOR DRAWERS.AUTO HINGES OF HETTICH OR EQUIVALENT.				
7	**CONSOLE UNIT** Signature and Stamp of Bidder	**1.00**	**NOS.**	**90,000.00**	**90,000.00**

	PROVIDING & FIXING CONSOLE UNIT OF 1800MMX450MMX730MM(H) , UNIT TOP IN MICHEAL ANGELO MARBLE(ABOUT RS.950/- PER SFT),SHUTTER & DRAWERS ARE MADE WITH 18MM THICK PLY IN PU FISHED,DRAWERS WITH TELESCOPIC CHANNEL,SHUTTER WITH MAGNET & AUTO HINGES OF HETTICH OR EQUIVALENT. M.S POWDER COATED LEGS.				
8	**DISPLAY RACK-1**	**80.00**	**SFT**	**2,900.00**	**2,32,000.00**
	PROVIDING & FIXING DISPLAY RACK OF 2620MMX210MMX2875MM(H) MADE WITH PLY & APPLY VENEER ON IT,FINISHED WITH MELAMINE POLISHED.DISPLAY RACK BACK CLADED WITH **NATURAL MARBLE(ABOUT RS.450/- PER SFT).**				
9	**DISPLAY RACK-2**	**26.00**	**SFT**	**2,900.00**	**75,400.00**
	PROVIDING & FIXING RACK SIZE OF 825MMX2875MM(H),IS MADE WITH PLY BOARD & MDF, **APPLY PU AND NATURAL MARBLE(ABOUT RS.450/- PER SFT) CLADING ON BOX.**				
10	**2 SEATER SOFA - CM'S CABIN**	**1.00**	**NOS.**	**90,000.00**	**90,000.00**
	1700MM X 800MM PROVIDING AND SUPPLYING SOFA TWO SEATER , FULLY UPHOLSTERED SOFA WITH MS POWDER COATED LEGS, SEAT AND BACK CUSHION MADE FROM HEIGH DENSITY M-FOAM WITH LEATHER COTTEN COVER, OF APPROVED MAKE WITH SEAT OF 150 MM THKL.AND BACK OF 100 MM THK. OF REQUIRED SIZE AS PER DRAWING, COVER IT WITH SELECTED TAPESTRY ON TOP AS PER DRAWING AND CLIENT CHOICE. CONSTRUCTION :KNOCKDOWN CONSTRUCTION.FINISH :EPOXY POWDER COATED TO THE THICKNESS OF 50 MICRONS (-1-- 10) . THE RATE INCLUDES COST OF ALL LABOUR,MATERIAL WITH ONE YEAR GAURANTEE FOR PRODUCT.				
11	**SINGLE SEATER SOFA - CM'S CABIN**	**1.00**	**NOS.**	**45,000.00**	**45,000.00**
	800MM X 800MM PROVIDING AND SUPPLYING SOFA SINGLE SEATER , FULLY UPHOLSTERED SOFA WITH MS POWDER COATED LEGS, SEAT AND BACK CUSHION MADE FROM HEIGH DENSITY M-FOAM WITH LEATHER COTTEN COVER, OF APPROVED MAKE WITH SEAT OF 150 MM THKL.AND BACK OF 100 MM THK. OF REQUIRED SIZE AS PER DRAWING, COVER IT WITH SELECTED TAPESTRY ON TOP AS PER DRAWING AND CLIENT CHOICE. CONSTRUCTION :KNOCKDOWN CONSTRUCTION.FINISH :EPOXY POWDER COATED TO THE THICKNESS OF 50 MICRONS (-1-- 10) THE RATE INCLUDES COST OF ALL LABOUR,MATERIAL WITH ONE YEAR GAURANTEE FOR PRODUCT.				
12	**COFFEE TABLE - CM'S CABIN**	**1.00**	**NOS.**	**60,000.00**	**60,000.00**
	900MM X 400MM PROVIDING AND FIXING TABLE WITH 12 MM. THICK TOUGHEN GLASSES WITH ROUND EDGE. REST ON SINGLE 3"DIA. M.S. PIPE WITH POWDER COAT FINISHED AND BOTTOM FOUR MS. PIPE LEG WITH PVC BUFFER AND TOP 0.5" DIA. M.S. FLANGE PLATE & S.S. STUD ON IT FOR GLASS FITTING, FOUR M.S. FLANGE .				
13	**CORNER TABLE - CM'S CABIN**	**1.00**	**NOS.**	**45,000.00**	**45,000.00**

Signature and Stamp of Bidder

	PROVIDING AND FIXING 500MM DIA. X 450MM (H) CORNER TABLE POWDER COATED M.S PIPE FRAME AND BOTTOM LEGS WITH PVC BUFFER AND 12MM THICK TOUGHEN GLASS ON TOP, FIXED WITH SIDE FLANGE.				
14	**WOODEN CEILING IN CABIN**	**82.00**	**SFT**	**950.00**	**77,900.00**
	PROVIDING AND FIXING PLY FRAMING BELOW AND COVERED WITH PLY,APPLYING VENEER (ABOUT RS.135/- PER SFT) ON PLY WITH GROOVES & MELAMINE POLISHED ON VENEER.				
15	**WOODEN CEILING IN FOYER**	**20.00**	**SFT**	**950.00**	**19,000.00**
	PROVIDING AND FIXING PLY FRAMING BELOW AND COVERED WITH PLY,APPLYING VENEER (ABOUT RS.135/- PER SFT) ON PLY WITH GROOVES & MELAMINE POLISHED ON VENEER.				
16	**PARTITION & PANELING**	**490.00**	**SFT**	**1,600.00**	**7,84,000.00**
	PROVIDING AND FIXING PARTITION MADE WITH ALUMINUM FRAMING,BOTH SIDE 12MM THICK PLY,PARTITION FINISHED WITH VENEER (ABOUT RS.135/- PER SFT), DESIGNED WITH GROOVES,FLUTED PANEL & METAL STRIPS AS PER SHOWN IN DRAWING. SIDE TABLE SIDE COLUMN COVERSD WITH FLUTED PATTA ON PLYBOARD PANELING.				
17	**PALMET**	**60.00**	**RFT**	**800.00**	**48,000.00**
	PROVIDING & FIXING PALMET ABOVE ALL GLAZED WINDOWS WITH 12MM PLY BOARD AND THE VENEER (ABOUT RS.135/- PER SFT) SURFACE WITH MELAMINE POLISHED ABOVE.				
18	**PROFILE DOORS**	**5.00**	**NOS.**	**60,000.00**	**3,00,000.00**
	PROVIDING & FIXING FLUTED GLASS DOOR WITH SLIM ALUMINUM POWDER COATED PROFILE,LOCK BODY & VENEER PANNEL WITH MELAMINE POLISHED FINISHED.				
19	**2 SEATER SOFA - ANT ROOM**	**1.00**	**NOS.**	**90,000.00**	**90,000.00**
	1700MM X 800MM PROVIDING AND SUPPLYING SOFA TWO SEATER , FULLY UPHOLSTERED SOFA WITH MS POWDER COATED LEGS, SEAT AND BACK CUSHION MADE FROM HEIGH DENSITY M-FOAM WITH LEATHER COTTEN COVER, OF APPROVED MAKE WITH SEAT OF 150 MM THKL.AND BACK OF 100 MM THK. OF REQUIRED SIZE AS PER DRAWING, COVER IT WITH SELECTED TAPESTRY ON TOP AS PER DRAWING AND CLIENT CHOICE. CONSTRUCTION :KNOCKDOWN CONSTRUCTION.FINISH :EPOXY POWDER COATED TO THE THICKNESS OF 50 MICRONS (-1-- 10) . THE RATE INCLUDES COST OF ALL LABOUR,MATERIAL WITH ONE YEAR GAURANTEE FOR PRODUCT.				
20	**SINGLE SEATER SOFA - ANT ROOM**	**1.00**	**NOS.**	**45,000.00**	**45,000.00**
	800MM X 800MM PROVIDING AND SUPPLYING SOFA SINGLE SEATER , FULLY UPHOLSTERED SOFA WITH MS POWDER COATED LEGS, SEAT AND BACK CUSHION MADE FROM HEIGH DENSITY M-FOAM WITH LEATHER COTTEN COVER, OF APPROVED MAKE WITH SEAT OF 150 MM THKL.AND BACK OF 100 MM THK. OF REQUIRED SIZE AS PER DRAWING, COVER IT WITH SELECTED TAPESTRY ON TOP AS PER DRAWING AND CLIENT CHOICE. CONSTRUCTION :KNOCKDOWN CONSTRUCTION.FINISH :EPOXY POWDER COATED TO THE THICKNESS OF 50 MICRONS (-1-- 10) THE RATE INCLUDES COST OF ALL LABOUR,MATERIAL WITH ONE				

	YEAR GAURANTEE FOR PRODUCT.				
21	**COFFEE TABLE - - ANT ROOM**	**1.00**	**NOS.**	**45,000.00**	**45,000.00**
	PROVIDING AND FIXING 500MM DIA. X 450MM (H) COFFEE TABLE POWDER COATED M.S PIPE FRAME AND BOTTOM LEGS WITH PVC BUFFER AND 12MM THICK TOUGHEN GLASS ON TOP, FIXED WITH SIDE FLANGE.				
22	**RECEPTION TABLE**	**1.00**	**NOS.**	**1,10,000.00**	**1,10,000.00**
	1400MM X 500MM X 750MM(H) PROVIDING & FIXING RECEPTION TABLE TOP IN CORIAN MARBLE, PLY BOARD BODY WITH VENEER & PU FINISHED SURFACE & LOCK&KEY DRAWER,TELESCOPIC CHANNEL OF HETTICH OR EQUIVALANT.				
23	**LOW HEIGHT FILE STORAGE**	**30.00**	**SFT**	**2,000.00**	**60,000.00**
	1100MM X 400MM X 1200(H) - 2 PROVIDING AND FIXING THE LOW HEIGHT STORAGE FOR 25MM THICK (PLYWOOD BOARD) POST FORMING LAMINATED TOP WITH 6MM THICK PLYWOOD AT BACKSIDE FINISHED WITH 1MM. THICK APPROVED LAMINATE, MADE OUT OF 18MM THICK PLYWOOD WITH EXTERIOR SIDE 1MM. AND INTERIOR SIDE 0.6MM. APPROVED LAMINATE. STORAGE UNIT BOX (MEASUREMENT SHOWN IN DRAWING) WITH WOODEN BEADING PATTI/PVC, LOCK. SHUTTER SHOULD BE MADE OF 18MM. THICK POST FORMING PLYWOOD WITH MAGNET, AUTO HINGES OF HETTICH OR EQUIVALENT.75MM LAMINATED BOTTOM, INCLUDING ALL MATERIALS AND LABOUR ETC. COMPLETE AS PER SHOWN IN DETAILED DRAWING.				
24	**2 SEATER SOFA - VIP WAITING**	**2.00**	**NOS.**	**80,000.00**	**1,60,000.00**
	1650MM X 850MM PROVIDING AND SUPPLYING SOFA TWO SEATER , FULLY UPHOLSTERED SOFA WITH MS POWDER COATED LEGS, SEAT AND BACK CUSHION MADE FROM HEIGH DENSITY M-FOAM WITH LEATHER COTTEN COVER, OF APPROVED MAKE WITH SEAT OF 150 MM THKL.AND BACK OF 100 MM THK. OF REQUIRED SIZE AS PER DRAWING, COVER IT WITH SELECTED TAPESTRY ON TOP AS PER DRAWING AND CLIENT CHOICE. CONSTRUCTION :KNOCKDOWN CONSTRUCTION.FINISH :EPOXY POWDER COATED TO THE THICKNESS OF 50 MICRONS (-1-- 10) . THE RATE INCLUDES COST OF ALL LABOUR,MATERIAL WITH ONE YEAR GAURANTEE FOR PRODUCT.				
25	**SOFA CHAIR - VIP WAITING**	**1.00**	**NOS.**	**40,000.00**	**40,000.00**
	850MM X 850MM PROVIDING AND SUPPLYING SOFA SINGLE SEATER , FULLY UPHOLSTERED SOFA WITH MS POWDER COATED LEGS, SEAT AND BACK CUSHION MADE FROM HEIGH DENSITY M-FOAM WITH LEATHER COTTEN COVER, OF APPROVED MAKE WITH SEAT OF 150 MM THKL.AND BACK OF 100 MM THK. OF REQUIRED SIZE AS PER DRAWING, COVER IT WITH SELECTED TAPESTRY ON TOP AS PER DRAWING AND CLIENT CHOICE. CONSTRUCTION :KNOCKDOWN CONSTRUCTION.FINISH :EPOXY POWDER COATED TO THE THICKNESS OF 50 MICRONS (-1-- 10) THE RATE INCLUDES COST OF ALL LABOUR,MATERIAL WITH ONE YEAR GAURANTEE Signature and Stamp of Bidder				

	FOR PRODUCT.				
26	**COFFEE TABLE - VIP WAITING**	**1.00**	**NOS.**	**45,000.00**	**45,000.00**
	PROVIDING AND FIXING 750MM DIA. X 450MM (H) COFFEE TABLE POWDER COATED M.S PIPE FRAME AND BOTTOM LEGS WITH PVC BUFFER AND 12MM THICK TOUGHEN GLASS ON TOP, FIXED WITH SIDE FLANGE.				
27	**CORNER TABLE - VIP WAITING**	**2.00**	**NOS.**	**40,000.00**	**80,000.00**
	PROVIDING AND FIXING 500MM DIA. X 450MM (H) COFFEE TABLE POWDER COATED M.S PIPE FRAME AND BOTTOM LEGS WITH PVC BUFFER AND 12MM THICK TOUGHEN GLASS ON TOP, FIXED WITH SIDE FLANGE.				
28	**PANTRY CABINET**	**38.00**	**SFT**	**2,500.00**	**95,000.00**
	PROVIDING AND FIXING PANTRY CABINET SIZE OF 1875MM X 675MM (H) IS MADE WITH (BWR) PLY BOARD SHUTTER AND DRAWER,BOTH SIDE LAMINATE. MAGNET & AUTO HINGES FOR SHUTTER,TELESCOPIC CHANNELS OF HETTICH OR EQUIVALENT. OVERHEAD CABINET SIZE 1400MMX700MMX300MM. OVERHEAD CABINET 1400MMX700MM(H)X300MM(D) MADE OUT OF 18MM THICK PLY BOARD EXTERIOR SIDE 1MM LAMINET AND INSIDE 0.6MM LAMINATE.SHUTTER SHOULD BE MADE OF 18MM THICK PLYWOOD WITH LAMINATE,WOODEN BEADING PATTI/PVC , MAGNET & AUTO HINGES OF HETTICH OR EQUIVALENT.INCLUDING ALL MATERIALS & LABOUR ETC.				
29	**FLOOR LAMP**	**1.00**	**NOS.**	**15,000.00**	**15,000.00**
30	**COAT HANGER**	**1.00**	**NOS.**	**8,000.00**	**8,000.00**
31	**RUG - 1500MMX1200MM**	**1.00**	**NOS.**	**14,000.00**	**14,000.00**
32	**DECOR - ART PIECES & PAINTING**	**1.00**	**Lump Sum**	**3,00,000.00**	**3,00,000.00**
	ART PIECES (15 NOS.), FLOWER POTS (15 NOS.) & PAINTING(30 NOS.)				
	SECOND FLOOR				
33	**G.M TABLE**	**1.00**	**NOS.**	**1,15,000.00**	**1,15,000.00**
	PROVIDING & FIXING TABLE SIZE OF 2000MMX 750MMX750MM(H),TABLE TOP IN CORIAN MARBLE(ABOUT RS.800/- PER SFT),COMMERCIAL PLY BODY WITH PU FINISHED ,VENEERED FRONTPANEL & FOOTREST BELOW.				
34	**SIDE TABLE**	**1.00**	**NOS.**	**30,000.00**	**30,000.00**
	PROVIDING & FIXING TABLE SIZE OF 900MMX450MMX750MM(H) ,TABLE TOP IN 1MM LAMINATE(MAKE - CENTURY,MIKASA,GREENLAM RS.1950 PER SHEET-8'X4'), DRAWER & SHUTTERS MADE FROM 18MM THICK PLY WITH MAGNET,MULTIPLE DRAWERS, LOCK AND TELESCOPIC CHANNEL FOR DRAWERS.AUTO HINGES OF HETTICH OR EQUIVALENT.				
35	**SINGLE SEATER SOFA - GM'S CABIN**	**2.00**	**NOS.**	**40,000.00**	**80,000.00**

Signature and Stamp of Bidder

	PROVIDING AND SUPPLYING SOFA SINGLE SEATER , FULLY UPHOLSTERED SOFA WITH MS POWDER COATED LEGS, SEAT AND BACK CUSHION MADE FROM HEIGH DENSITY M-FOAM WITH LEATHER COTTEN COVER, OF APPROVED MAKE WITH SEAT OF 150 MM THKL.AND BACK OF 100 MM THK. OF REQUIRED SIZE AS PER DRAWING, COVER IT WITH SELECTED TAPESTRY ON TOP AS PER DRAWING AND CLIENT CHOICE. CONSTRUCTION :KNOCKDOWN CONSTRUCTION.FINISH :EPOXY POWDER COATED TO THE THICKNESS OF 50 MICRONS (-1-- 10) THE RATE INCLUDES COST OF ALL LABOUR,MATERIAL WITH ONE YEAR GAURANTEE FOR PRODUCT.				
36	**COFFEE TABLE - GM'S CABIN**	**2.00**	**NOS.**	**45,000.00**	**90,000.00**
	PROVIDING AND FIXING THE SQUARE TABLE OF 500MMX500MM WITH 12 MM. THICK TOUGHEN GLASSES WITH ROUND EDGE. REST ON FOUR 1"DIA. M.S. PIPE WITH POWDER COAT FINISHED AND BOTTOM FOUR MS. PIPE LEG WITH PVC BUFFER AND TOP 0.5" DIA. M.S. FLANGE PLATE & S.S. STUD ON IT FOR GLASS FITTING.				
37	**DISPLAY RACK - GM'S CABIN**	**30.00**	**SFT**	**2,500.00**	**75,000.00**
	PROVIDING & FIXING RACK SIZE OF 905MM X 2800MM(H),IS MADE WITH PLY,LAMINATE SURFACE (MAKE - CENTURY,MIKASA,GREENLAM RS.1950 PER SHEET-8'X4') AND LED PROFILE LIGHTS INSIDE NICHES.				
38	**PROFILE DOOR**	**2.00**	**NOS.**	**60,000.00**	**1,20,000.00**
	PROVIDING & FIXING FLUTED GLASS DOOR WITH SLIM ALUMINUM POWDER COATED PROFILE,LOCK BODY & VENEER PANNEL WITH MELAMINE POLISHED FINISHED.				
39	**WORK STATION**	**2.00**	**NOS.**	**1,45,000.00**	**2,90,000.00**
	2450MMX1250MMX750MM(H) PROVIDING & FIXING THE WORK STATION TABLE TOP 25MM THICK IN LAMINATE WITH MATCHING EDGE BANDING & ALUMINUM FLIP UP PROVISION.M.S POWDER COATED "O" FRAME LEGS,WIRE MANAGER TREY BELOW TABLE,POWDER COATED KEY-BOARD TREY FIXED WITH M.S CLAMPS. SEPARATE DRAWER UNIT - 400MM X 450MM(D) X 600MM(H) IN LAMINATED SURFACE,WITH LOCK& KEY,HANDLE,AND TELESCOPIC CHANNEL OF HETTICH OR EQUIVALENT.				
40	**LOW HEIGHT FILE STORAGE**	**80.00**	**SFT**	**2,000.00**	**1,60,000.00**
	3050MM X 400MM X 1200MM(H) - 2 PROVIDING AND FIXING THE LOW HEIGHT STORAGE FOR 25MM THICK (PLYWOOD BOARD) POST FORMING LAMINATED TOP WITH 6MM THICK PLYWOOD AT BACKSIDE FINISHED WITH 1MM. THICK APPROVED LAMINATE, MADE OUT OF 18MM THICK PLYWOOD WITH EXTERIOR SIDE 1MM. AND INTERIOR SIDE 0.6MM. APPROVED LAMINATE. STORAGE UNIT BOX (MEASUREMENT SHOWN IN DRAWING) WITH WOODEN BEDDING PATTI/PVC. SHUTTER SHOULD BE MADE OF 18MM. THICK POST FORMING PLYWOOD WITH MAGNET,LOCK & AUTO HINGES OF HETTICH OR EQUIVALENT.FILE RACK BASE MADE WITH LAMINATED PLY BOARD.INCLUDING ALL MATERIALS AND LABOUR ETC. COMPLETE AS PER SHOWN IN DETAILED DRAWING.				
41	**LOW HEIGHT FILE STORAGE**	**35.00**	**SFT**	**2,000.00**	**70,000.00**

Signature and Stamp of Bidder

	1250MM X 400MM X 1200MM(H) - 2 PROVIDING AND FIXING THE LOW HEIGHT STORAGE FOR 25MM THICK (PLYWOOD BOARD) POST FORMING LAMINATED TOP WITH 6MM THICK PLYWOOD AT BACKSIDE FINISHED WITH 1MM. THICK APPROVED LAMINATE, MADE OUT OF 18MM THICK PLYWOOD WITH EXTERIOR SIDE 1MM. AND INTERIOR SIDE 0.6MM. APPROVED LAMINATE. STORAGE UNIT BOX (MEASUREMENT SHOWN IN DRAWING) WITH WOODEN BEDDING PATTI/PVC. SHUTTER SHOULD BE MADE OF 18MM. THICK POST FORMING PLYWOOD WITH MAGNET,LOCK & AUTO HINGES OF HETTICH OR EQUIVALENT.FILE RACK BASE MADE WITH LAMINATED PLY BOARD.INCLUDING ALL MATERIALS AND LABOUR ETC. COMPLETE AS PER SHOWN IN DETAILED DRAWING.				
42	**OVER HEAD FILE STORAGE**	**95.00**	**SFT**	**2,000.00**	**1,90,000.00**
	2450MM X 375MM X 900MM(H) - 4 PROVIDING AND FIXING THE HANGING FILE STORAGE FOR 18MM THICK (PLYWOOD BOARD) POST FORMING LAMINATED TOP WITH 6MM THICK PLYWOOD AT BACKSIDE FINISHED WITH 1MM. THICK APPROVED LAMINATE, MADE OUT OF 18MM THICK PLYWOOD WITH EXTERIOR SIDE 1MM. AND INTERIOR SIDE 0.6MM. APPROVED LAMINATE. STORAGE UNIT BOX (MEASUREMENT SHOWN IN DRAWING) WITH WOODEN BEDDING PATTI/PVC. SHUTTER SHOULD BE MADE OF 18MM. THICK POST FORMING PLYWOOD WITH MAGNET, AUTO HINGES OF HETTICH OR EQUIVALENT. FOR HANGING THE FILE STORAGE FROM SLAB USED 25MMX25MM M.S SQUARE TUBE FRAMING AS PER SHOWN IN DRAWING.INCLUDING ALL MATERIALS AND LABOUR ETC. COMPLETE AS PER SHOWN IN DETAILED DRAWING.				
43	**FULL HEIGHT FILE STORAGE**	**55.00**	**SFT**	**2,000.00**	**1,10,000.00**
	2400MM X 450MM X 2100MM(H) PROVIDING AND FIXING THE FULL HEIGHT STORAGE FOR 18MM THICK (PLYWOOD BOARD) POST FORMING LAMINATED WITH 6MM THICK PLYWOOD AT BACKSIDE FINISHED WITH 1MM. THICK APPROVED LAMINATE, MADE OUT OF 18MM THICK PLYWOOD WITH EXTERIOR SIDE 1MM. AND INTERIOR SIDE 0.6MM. APPROVED LAMINATE. STORAGE UNIT BOX (MEASUREMENT SHOWN IN DRAWING) WITH WOODEN BEDDING PATTI/PVC. SHUTTER SHOULD BE MADE OF 18MM. THICK POST FORMING PLYWOOD WITH MAGNET,LOCK,AUTO HINGES OF HETTICH OR EQUIVALENT. INCLUDING ALL MATERIALS AND LABOUR ETC. COMPLETE AS PER SHOWN IN DETAILED DRAWING.				
44	**FULL HEIGHT FILE STORAGE**	**35.00**	**SFT**	**2,000.00**	**70,000.00**
	1495MM X 450MM X 2100MM(H) PROVIDING AND FIXING THE FULL HEIGHT STORAGE FOR 18MM THICK (PLYWOOD BOARD) POST FORMING LAMINATED WITH 6MM THICK PLYWOOD AT BACKSIDE FINISHED WITH 1MM. THICK APPROVED LAMINATE, MADE OUT OF 18MM THICK PLYWOOD WITH EXTERIOR SIDE 1MM. AND INTERIOR SIDE 0.6MM. APPROVED LAMINATE. STORAGE UNIT BOX (MEASUREMENT SHOWN IN DRAWING) WITH WOODEN BEDDING PATTI/PVC. SHUTTER SHOULD BE MADE OF 18MM. THICK POST FORMING PLYWOOD WITH MAGNET,LOCK,AUTO HINGES OF HETTICH OR EQUIVALENT. INCLUDING ALL Signature and Stamp of Bidder				

	MATERIALS AND LABOUR ETC. COMPLETE AS PER SHOWN IN DETAILED DRAWING.				
45	**AGM'S TABLE**	**1.00**	**NOS.**	**45,000.00**	**45,000.00**
	1650MM X 675MM X 750MM(H) PROVIDING & FIXING AGM TABLE TOP IN LAMINATED PLY BOARD, M.S POWDER COATED "O" FRAME LEG ONE SIDE & OTHER SIDE LAMINATED PLY BOARD,WITH POWDER COATED KEY-BOARD TREY FIXED WITH M.S CLAMP.FRONT PANEL IN PLY BOARD WITH BOTH SIDE 1MM LAMINATE.				
46	**SIDE TABLE**	**9.00**	**SFT**	**1,950.00**	**17,550.00**
	1000MM X 400MM X 750MM(H) PROVIDING & FIXING TABLE SIZE OF 1000MM X 400MM X 750MM(H) ,TABLE TOP IN 1MM LAMINATE, DRAWER & SHUTTERS MADE FROM 18MM THICK PLY WITH MAGNET,MULTIPLE DRAWER, LOCK AND TELESCOPIC CHANNEL FOR DRAWERS.AUTO HINGES OF HETTICH OR EQUIVALENT.				
47	**LOW HEIGHT FILE STORAGE**	**12.00**	**SFT**	**2,000.00**	**24,000.00**
	1500MM X 400MM X 750MM(H) PROVIDING AND FIXING THE LOW HEIGHT STORAGE FOR 25MM THICK (PLYWOOD BOARD) POST FORMING LAMINATED TOP WITH 6MM THICK PLYWOOD AT BACKSIDE FINISHED WITH 1MM. THICK APPROVED LAMINATE, MADE OUT OF 18MM THICK PLYWOOD WITH EXTERIOR SIDE 1MM. AND INTERIOR SIDE 0.6MM. APPROVED LAMINATE. STORAGE UNIT BOX (MEASUREMENT SHOWN IN DRAWING) WITH WOODEN BEDDING PATTI/PVC. SHUTTER SHOULD BE MADE OF 18MM. THICK POST FORMING PLYWOOD WITH MAGNET,LOCK & AUTO HINGES OF HETTICH OR EQUIVALENT.FILE RACK BASE MADE WITH LAMINATED PLY BOARD.INCLUDING ALL MATERIALS AND LABOUR ETC. COMPLETE AS PER SHOWN IN DETAILED DRAWING.				
48	**PEON TABLES**	**2.00**	**NOS.**	**25,000.00**	**50,000.00**
	PROVIDING AND FIXING 1MM LAMINATED TOP & M.S POWDER COATED "O" FRAME LEGS.				
49	**WOODEN CEILING IN FOYER**	**20.00**	**SFT**	**800.00**	**16,000.00**
	PROVIDING AND FIXING PLY FRAMING BELOW AND COVERED WITH PLY,APPLYING VENEER **(ABOUT RS.135/- PER SFT) ON PLY WITH GROOVES & . ON VENEER.**				
50	**PARTITION**	**350.00**	**SFT**	**1,400.00**	**4,90,000.00**
	PROVIDING AND FIXING PARTITION MADE WITH ALUMINUM FRAMING,BOTH SIDE 12MM THICK PLY,CUTOUT FOR GLASS,BEADING PATTI,GROOVES,METAL STRIP DESIGN & PARTITION SURFACE IN LAMINATE **(MAKE - CENTURY,MIKASA,GREENLAM RS.1950 PER SHEET-8'X4').**				
51	**PALMET**	**60.00**	**RFT**	**700.00**	**42,000.00**
	PROVIDING & FIXING PALMET ABOVE ALL GLAZED WINDOWS WITH 18MM THICK PLY BOARD WITH LAMINATE **(MAKE - CENTURY,MIKASA,GREENLAM RS.1950 PER SHEET-8'X4') SURFACE.**				
52	**PANTRY CABINET**	**38.00**	**SFT**	**2,500.00**	**95,000.00**

Signature and Stamp of Bidder

	PROVIDING AND FIXING PANTRY CABINET SIZE OF 1710MM X 675MM (H) IS MADE WITH (BWR) PLY BOARD SHUTTER AND DRAWER,BOTH SIDE LAMINATE. MAGNET & AUTO HINGES FOR SHUTTER,TELESCOPIC CHANNELS OF HETTICH OR EQUIVALENT. OVERHEAD CABINET 1400MMX700MM(H)X300MM(D) MADE OUT OF 18MM THICK PLY BOARD EXTERIOR SIDE 1MM LAMINET AND INSIDE 0.6MM LAMINATE.SHUTTER SHOULD BE MADE OF 18MM THICK PLYWOOD WITH LAMINATE,WOODEN BEADING PATTI/PVC , MAGNET & AUTO HINGES OF HETTICH OR EQUIVALENT.INCLUDING ALL MATERIALS & LABOUR ETC.				
	THIRD FLOOR				
53	**AGM'S TABLE**	**3.00**	**NOS.**	**45,000.00**	**1,35,000.00**
	1500MM X 600MM X 750MM(H) PROVIDING & FIXING AGM TABLE TOP IN LAMINATED PLY BOARD, M.S POWDER COATED "O" FRAME LEG ONE SIDE & OTHER SIDE LAMINATED PLY BOARD,WITH POWDER COATED KEY-BOARD TREY FIXED WITH M.S CLAMP.FRONT PANEL IN PLY BOARD WITH BOTH SIDE 1MM LAMINATE(MAKE - CENTURY,MIKASA,GREENLAM RS.1950 PER SHEET-8'X4').				
54	**SIDE TABLE**	**3.00**	**NOS.**	**17,500.00**	**52,500.00**
	PROVIDING & FIXING TABLE SIZE OF 1100MM X 400MM X 750MM(H) ,TABLE TOP IN 1MM LAMINATE, DRAWER & SHUTTERS MADE FROM 18MM THICK PLY WITH MAGNET,MULTIPLE DRAWERS, LOCK AND TELESCOPIC CHANNEL FOR DRAWERS.AUTO HINGES OF HETTICH OR EQUIVALENT.				
55	**LOW HEIGHT FILE STORAGE**	**22.00**	**SFT**	**2,000.00**	**44,000.00**
	1675MM X 400MM X 1200MM(H) PROVIDING AND FIXING THE LOW HEIGHT STORAGE FOR 25MM THICK (PLYWOOD BOARD) POST FORMING LAMINATED TOP WITH 6MM THICK PLYWOOD AT BACKSIDE FINISHED WITH 1MM. THICK APPROVED LAMINATE, MADE OUT OF 18MM THICK PLYWOOD WITH EXTERIOR SIDE 1MM. AND INTERIOR SIDE 0.6MM. APPROVED LAMINATE. STORAGE UNIT BOX (MEASUREMENT SHOWN IN DRAWING) WITH WOODEN BEDDING PATTI/PVC. SHUTTER SHOULD BE MADE OF 18MM. THICK POST FORMING PLYWOOD WITH MAGNET,LOCK & AUTO HINGES OF HETTICH OR EQUIVALENT.FILE RACK BASE MADE WITH LAMINATED PLY BOARD.INCLUDING ALL MATERIALS AND LABOUR ETC. COMPLETE AS PER SHOWN IN DETAILED DRAWING.				
56	**LOW HEIGHT FILE STORAGE**	**40.00**	**SFT**	**2,000.00**	**80,000.00**
	1500MM X 400MM X 1200MM(H) - 2 PROVIDING AND FIXING THE LOW HEIGHT STORAGE FOR 25MM THICK (PLYWOOD BOARD) POST FORMING LAMINATED TOP WITH 6MM THICK PLYWOOD AT BACKSIDE FINISHED WITH 1MM. THICK APPROVED LAMINATE, MADE OUT OF 18MM THICK PLYWOOD WITH EXTERIOR SIDE 1MM. AND INTERIOR SIDE 0.6MM. APPROVED LAMINATE. STORAGE UNIT BOX (MEASUREMENT SHOWN IN DRAWING) WITH WOODEN BEDDING PATTI/PVC. SHUTTER SHOULD BE MADE OF 18MM. THICK POST FORMING PLYWOOD WITH MAGNET,LOCK & AUTO HINGES OF HETTICH OR EQUIVALENT.FILE RACK BASE MADE WITH LAMINATED PLY BOARD.INCLUDING ALL MATERIALS AND LABOUR ETC. COMPLETE AS PER SHOWN IN DETAILED Signature and Stamp of Bidder				

	DRAWING.				
57	**LOW HEIGHT FILE STORAGE**	**12.00**	**SFT**	**2,000.00**	**24,000.00**
	1500MM X 400MM X750MM(H) PROVIDING AND FIXING THE LOW HEIGHT STORAGE FOR 25MM THICK (PLYWOOD BOARD) POST FORMING LAMINATED TOP WITH 6MM THICK PLYWOOD AT BACKSIDE FINISHED WITH 1MM. THICK APPROVED LAMINATE, MADE OUT OF 18MM THICK PLYWOOD WITH EXTERIOR SIDE 1MM. AND INTERIOR SIDE 0.6MM. APPROVED LAMINATE. STORAGE UNIT BOX (MEASUREMENT SHOWN IN DRAWING) WITH WOODEN BEDDING PATTI/PVC, LOCK AND TELESCOPIC CHANNEL. SHUTTER SHOULD BE MADE OF 18MM. THICK POST FORMING PLYWOOD WITH MAGNETLOCK,75MM LAMINATED PLY BOARD BOTTOM, AUTO HINGES OF HETTICH OR EQUIVALENT. INCLUDING ALL MATERIALS AND LABOUR ETC. COMPLETE AS PER SHOWN IN DETAILED DRAWING.				
58	**LOW HEIGHT FILE STORAGE**	**11.00**	**SFT**	**2,000.00**	**22,000.00**
	1350MM X 400MM X750MM(H) PROVIDING AND FIXING THE LOW HEIGHT STORAGE FOR 25MM THICK (PLYWOOD BOARD) POST FORMING LAMINATED TOP WITH 6MM THICK PLYWOOD AT BACKSIDE FINISHED WITH 1MM. THICK APPROVED LAMINATE, MADE OUT OF 18MM THICK PLYWOOD WITH EXTERIOR SIDE 1MM. AND INTERIOR SIDE 0.6MM. APPROVED LAMINATE. STORAGE UNIT BOX (MEASUREMENT SHOWN IN DRAWING) WITH WOODEN BEDDING PATTI/PVC. SHUTTER SHOULD BE MADE OF 18MM. THICK POST FORMING PLYWOOD WITH MAGNET,LOCK & AUTO HINGES OF HETTICH OR EQUIVALENT.FILE RACK BASE MADE WITH LAMINATED PLY BOARD.INCLUDING ALL MATERIALS AND LABOUR ETC. COMPLETE AS PER SHOWN IN DETAILED DRAWING.				
59	**LOW HEIGHT FILE STORAGE**	**10.00**	**SFT**	**2,000.00**	**20,000.00**
	1200MM X 400MM X750MM(H) PROVIDING AND FIXING THE LOW HEIGHT STORAGE FOR 25MM THICK (PLYWOOD BOARD) POST FORMING LAMINATED TOP WITH 6MM THICK PLYWOOD AT BACKSIDE FINISHED WITH 1MM. THICK APPROVED LAMINATE, MADE OUT OF 18MM THICK PLYWOOD WITH EXTERIOR SIDE 1MM. AND INTERIOR SIDE 0.6MM. APPROVED LAMINATE. STORAGE UNIT BOX (MEASUREMENT SHOWN IN DRAWING) WITH WOODEN BEDDING PATTI/PVC. SHUTTER SHOULD BE MADE OF 18MM. THICK POST FORMING PLYWOOD WITH MAGNET,LOCK & AUTO HINGES OF HETTICH OR EQUIVALENT.FILE RACK BASE MADE WITH LAMINATED PLY BOARD.INCLUDING ALL MATERIALS AND LABOUR ETC. COMPLETE AS PER SHOWN IN DETAILED DRAWING.				
60	**LOW PARTITION**	**91.00**	**SFT**	**1,400.00**	**1,27,400.00**
	PROVIDING AND FIXING PARTITION MADE WITH ALUMINUM FRAMING,BOTH SIDE 12MM THICK PLY,LAMINATE SURFACE (MAKE - CENTURY,MIKASA,GREENLAM RS.1950 PER SHEET-8'X4') 18MM THICK WOODEN PATTI ON TOP WITH 4MM GROOVE.				
61	**WORK STATION**	**1.00**	**NOS.**	**1,45,000.00**	**1,45,000.00**

Signature and Stamp of Bidder

	2450MMX1250MMX750MM(H) PROVIDING & FIXING THE WORK STATION TABLE TOP 25MM THICK IN LAMINATE WITH MATCHING EDGE BANDING & ALUMINUM FLIP UP PROVISION.M.S POWDER COATED "O" FRAME LEGS,WIRE MANAGER TREY BELOW TABLE,POWDER COATED KEY-BOARD TREY FIXED WITH M.S CLAMPS. SEPARATE DRAWER UNIT - 400MM X 450MM(D) X 600MM(H) IN LAMINATED SURFACE,WITH LOCK& KEY,HANDLE,AND TELESCOPIC CHANNEL OF HETTICH OR EQUIVALENT.				
62	**CONFERENCE TABLE**	**1.00**	**NOS.**	**65,000.00**	**65,000.00**
	2300MM X 700MM X 750MM(H) PROVIDING & FIXING THE CONFERENCE TABLE TOP 50MM THICK IN LAMINAE(MAKE - CENTURY,MIKASA,GREENLAM RS.1950 PER SHEET-8'X4') WITH MATCHING EDGE BANDING & ALUMINUM FLIP UP PROVISION.M.S POWDER COATED LEGS,WIRE MANAGER TREY BELOW TABLE,SHOWN AS PER DRAWING.				
63	**LOW HEIGHT FILE STORAGE**	**31.00**	**SFT**	**2,000.00**	**62,000.00**
	2400MM X 400MM X 1200MM(H) PROVIDING AND FIXING THE LOW HEIGHT STORAGE FOR 25MM THICK (PLYWOOD BOARD) POST FORMING LAMINATED TOP WITH 6MM THICK PLYWOOD AT BACKSIDE FINISHED WITH 1MM. THICK APPROVED LAMINATE, MADE OUT OF 18MM THICK PLYWOOD WITH EXTERIOR SIDE 1MM. AND INTERIOR SIDE 0.6MM. APPROVED LAMINATE. STORAGE UNIT BOX (MEASUREMENT SHOWN IN DRAWING) WITH WOODEN BEDDING PATTI/PVC. SHUTTER SHOULD BE MADE OF 18MM. THICK POST FORMING PLYWOOD WITH MAGNET,LOCK & AUTO HINGES OF HETTICH OR EQUIVALENT.FILE RACK BASE MADE WITH LAMINATED PLY BOARD.INCLUDING ALL MATERIALS AND LABOUR ETC. COMPLETE AS PER SHOWN IN DETAILED DRAWING.				
64	**OVERHEAD FILE STORAGE**	**47.00**	**SFT**	**2,000.00**	**94,000.00**
	2400MM X 375MM X 900MM(H) - 2 PROVIDING AND FIXING THE HANGING FILE STORAGE FOR 18MM THICK (PLYWOOD BOARD) POST FORMING LAMINATED TOP WITH 6MM THICK PLYWOOD AT BACKSIDE FINISHED WITH 1MM. THICK APPROVED LAMINATE, MADE OUT OF 18MM THICK PLYWOOD WITH EXTERIOR SIDE 1MM. AND INTERIOR SIDE 0.6MM. APPROVED LAMINATE. STORAGE UNIT BOX (MEASUREMENT SHOWN IN DRAWING) WITH WOODEN BEDDING PATTI/PVC. SHUTTER SHOULD BE MADE OF 18MM. THICK POST FORMING PLYWOOD WITH MAGNET, AUTO HINGES OF HETTICH OR EQUIVALENT. FOR HANGING THE FILE STORAGE FROM SLAB USED 25MMX25MM M.S SQUARE TUBE FRAMING AS PER SHOWN IN DRAWING.INCLUDING ALL MATERIALS AND LABOUR ETC. COMPLETE AS PER SHOWN IN DETAILED DRAWING.				
65	**FULL HEIGHT FILE STORAGE**	**69.00**	**SFT**	**2,000.00**	**1,38,000.00**
	3045MM X 400MM X 2100MM(H) PROVIDING AND FIXING THE FULL HEIGHT STORAGE FOR 18MM THICK (PLYWOOD BOARD) POST FORMING LAMINATED WITH 6MM THICK PLYWOOD AT BACKSIDE FINISHED WITH 1MM. THICK APPROVED LAMINATE, MADE OUT OF 18MM THICK PLYWOOD WITH EXTERIOR SIDE 1MM. AND INTERIOR SIDE 0.6MM. APPROVED LAMINATE. STORAGE UNIT BOX Signature and Stamp of Bidder				

	(MEASUREMENT SHOWN IN DRAWING) WITH WOODEN BEDDING PATTI/PVC. SHUTTER SHOULD BE MADE OF 18MM. THICK POST FORMING PLYWOOD WITH MAGNET,LOCK,AUTO HINGES OF HETTICH OR EQUIVALENT. INCLUDING ALL MATERIALS AND LABOUR ETC. COMPLETE AS PER SHOWN IN DETAILED DRAWING AND INSTRUCTIONS OF ENGINEER-IN-CHARGE.				
66	**PROFILE DOOR**	**2.00**	**NOS.**	**60,000.00**	**1,20,000.00**
	PROVIDING & FIXING FLUTED GLASS DOOR WITH SLIM ALUMINUM POWDER COATED PROFILE,LOCK BODY & VENEER PANNEL WITH MELAMINE POLISHED FINISHED.				
67	**PARTITION**	**402.00**	**SFT**	**1,400.00**	**5,62,800.00**
	PROVIDING AND FIXING PARTITION MADE WITH ALUMINUM FRAMING,BOTH SIDE 12MM THICK PLY,GROOVES,METAL STRIP & PARTITION SURFACE IN LAMINATE (**MAKE - CENTURY,MIKASA,GREENLAM RS.1950 PER SHEET-8'X4').**				
68	**PANTRY DOOR**	**1.00**	**NOS.**	**21,000.00**	**21,000.00**
	PROVIDING AND FIXING 30MM THICK FLUSH DOOR WITH BOTH SIDE 1MM LAMINATE,HINGES, HANDLE & DOOR CLOSER OF **HETTICH OR EQUIVALENT**.				
69	**PANTRY CABINET**	**38.00**	**SFT**	**2,500.00**	**95,000.00**
	PROVIDING AND FIXING PANTRY CABINET SIZE OF 1710MM X 675MM (H) IS MADE WITH (BWR) PLY BOARD SHUTTER AND DRAWER,BOTH SIDE LAMINATE. MAGNET & AUTO HINGES FOR SHUTTER,TELESCOPIC CHANNELS OF HETTICH OR EQUIVALENT.OVERHEAD CABINET 1500MMX700MMX350MM OVERHEAD CABINET 1400MMX700MM(H)X300MM(D) MADE OUT OF 18MM THICK PLY BOARD EXTERIOR SIDE 1MM LAMINET AND INSIDE 0.6MM LAMINATE.SHUTTER SHOULD BE MADE OF 18MM THICK PLYWOOD WITH LAMINATE,WOODEN BEADING PATTI/PVC , MAGNET & AUTO HINGES OF **HETTICH OR EQUIVALENT**. INCLUDING ALL MATERIALS & LABOUR ETC.				
70	**FULL HEIGHT FILE STORAGE**	**33.00**	**SFT**	**2,000.00**	**66,000.00**
	1420MM X 300MM X 2100MM(H) PROVIDING AND FIXING THE FULL HEIGHT STORAGE FOR 18MM THICK (PLYWOOD BOARD) POST FORMING LAMINATED WITH 6MM THICK PLYWOOD AT BACKSIDE FINISHED WITH 1MM. THICK APPROVED LAMINATE, MADE OUT OF 18MM THICK PLYWOOD WITH EXTERIOR SIDE 1MM. AND INTERIOR SIDE 0.6MM. APPROVED LAMINATE. STORAGE UNIT BOX (MEASUREMENT SHOWN IN DRAWING) WITH WOODEN BEDDING PATTI/PVC. SHUTTER SHOULD BE MADE OF 18MM. THICK POST FORMING PLYWOOD WITH MAGNET,LOCK,AUTO HINGES OF **HETTICH OR EQUIVALENT**. INCLUDING ALL MATERIALS AND LABOUR ETC. COMPLETE AS PER SHOWN IN DETAILED DRAWING.				
71	**WOODEN CEILING IN FOYER**	**20.00**	**SFT**	**800.00**	**16,000.00**
	PROVIDING AND FIXING PLY FRAMING BELOW AND COVERED WITH PLY,APPLYING VENEER (ABOUT RS.135/- PER SFT) ON PLY WITH GROOVES & MELAMINE POLISHED ON VENEER.				
72	**PALMET**	**60.00**	**RFT**	**700.00**	**42,000.00**

Signature and Stamp of Bidder

	PROVIDING & FIXING PALMET ABOVE ALL GLAZED WINDOWS WITH 18MM THICK PLY BOARD WITH LAMINATE **(MAKE – CENTURY,MIKASA,GREENLAM RS.1950 PER SHEET-8'X4') SURFACE.**				
	FOURTH FLOOR				
73	**AGM'S TABLE**	**1.00**	**NOS.**	**45,000.00**	**45,000.00**
	1500MM X 600MM X 750MM(H PROVIDING & FIXING AGM TABLE TOP IN LAMINATED PLY BOARD, M.S POWDER COATED "O" FRAME LEG ONE SIDE & OTHER SIDE LAMINATED PLY BOARD,WITH POWDER COATED KEY-BOARD TREY FIXED WITH M.S CLAMP.FRONT PANEL IN PLY BOARD WITH BOTH SIDE 1MM LAMINATE.				
74	**SIDE TABLE**	**1.00**	**NOS.**	**17,500.00**	**17,500.00**
	PROVIDING & FIXING TABLE SIZE OF 1000MM X 400MM X 750MM(H) ,TABLE TOP IN 1MM LAMINATE, DRAWER & SHUTTERS MADE FROM 18MM THICK PLY WITH MAGNET,MULTIPLE DRAWERS, LOCK AND TELESCOPIC CHANNEL FOR DRAWERS.AUTO HINGES OF **HETTICH OR EQUIVALENT.**				
75	**OFFICER'S TABLE**	**2.00**	**NOS.**	**45,000.00**	**90,000.00**
	1500MM X 600MM X 750MM(H) PROVIDING & FIXING OFFICER'S TABLE TOP IN LAMINATED PLY BOARD, M.S POWDER COATED "O" FRAME LEG ONE SIDE & OTHER SIDE LAMINATED PLY BOARD,WITH POWDER COATED KEY-BOARD TREY FIXED WITH M.S CLAMP.FRONT PANEL IN PLY BOARD WITH BOTH SIDE 1MM LAMINATE.				
76	**SIDE TABLE**	**2.00**	**NOS.**	**17,500.00**	**35,000.00**
	PROVIDING & FIXING TABLE SIZE OF 1000MM X 400MM X 750MM(H) ,TABLE TOP IN 1MM LAMINATE, DRAWER & SHUTTERS MADE FROM 18MM THICK PLY WITH MAGNET,MULTIPLE DRAWERS, LOCK AND TELESCOPIC CHANNEL FOR DRAWERS. **AUTO HINGES OF HETTICH OR EQUIVALENT.**				
77	**WORK STATION**	**1.00**	**NOS.**	**75,000.00**	**75,000.00**
	2450MM X 600MM X 750MM(H) PROVIDING & FIXING THE WORK STATION TABLE TOP 25MM THICK IN LAMINATE WITH MATCHING EDGE BANDING & ALUMINUM FLIP UP PROVISION.M.S POWDER COATED "O" FRAME LEGS,WIRE MANAGER TREY BELOW TABLE,POWDER COATED KEY-BOARD TREY FIXED WITH M.S CLAMPS. SEPARATE DRAWER UNIT - 400MM X 450MM(D) X 600MM(H) IN LAMINATED SURFACE,WITH LOCK& KEY,HANDLE,AND **TELESCOPIC CHANNEL OF HETTICH OR EQUIVALENT.**				
78	**WORK STATION**	**1.00**	**NOS.**	**1,15,000.00**	**1,15,000.00**
	3700MM X 600MM X 750MM(H) PROVIDING & FIXING THE WORK STATION TABLE TOP 25MM THICK IN LAMINATE WITH MATCHING EDGE BANDING & ALUMINUM FLIP UP PROVISION.M.S POWDER COATED "O" FRAME LEGS,WIRE MANAGER TREY BELOW TABLE,POWDER COATED KEY-BOARD TREY FIXED WITH M.S CLAMPS. SEPARATE DRAWER UNIT - 400MM X 450MM(D) X 600MM(H) Signature and Stamp of Bidder				

	IN LAMINATED SURFACE,WITH LOCK& KEY,HANDLE, AND **TELESCOPIC CHANNEL OF HETTICH OR EQUIVALENT.**				
79	**LOW HEIGHT FILE STORAGE**	**40.00**	**SFT**	**2,000.00**	**80,000.00**
	1500MM X 400MM X 1200MM(H) - 2 PROVIDING AND FIXING THE LOW HEIGHT STORAGE FOR 25MM THICK (PLYWOOD BOARD) POST FORMING LAMINATED TOP WITH 6MM THICK PLYWOOD AT BACKSIDE FINISHED WITH 1MM. THICK APPROVED LAMINATE, MADE OUT OF 18MM THICK PLYWOOD WITH EXTERIOR SIDE 1MM. AND INTERIOR SIDE 0.6MM. APPROVED LAMINATE. STORAGE UNIT BOX (MEASUREMENT SHOWN IN DRAWING) WITH WOODEN BEDDING PATTI/PVC. SHUTTER SHOULD BE MADE OF 18MM. THICK POST FORMING PLYWOOD WITH MAGNET,LOCK & AUTO HINGES OF **HETTICH OR EQUIVALENT**.FILE RACK BASE MADE WITH LAMINATED PLY BOARD.INCLUDING ALL MATERIALS AND LABOUR ETC. COMPLETE AS PER SHOWN IN DETAILED DRAWING.				
80	**LOW HEIGHT FILE STORAGE**	**31.00**	**SFT**	**2,000.00**	**62,000.00**
	2400MM X 400MM X 1200MM(H) - 2 PROVIDING AND FIXING THE LOW HEIGHT STORAGE FOR 25MM THICK (PLYWOOD BOARD) POST FORMING LAMINATED TOP WITH 6MM THICK PLYWOOD AT BACKSIDE FINISHED WITH 1MM. THICK APPROVED LAMINATE, MADE OUT OF 18MM THICK PLYWOOD WITH EXTERIOR SIDE 1MM. AND INTERIOR SIDE 0.6MM. APPROVED LAMINATE. STORAGE UNIT BOX (MEASUREMENT SHOWN IN DRAWING) WITH WOODEN BEDDING PATTI/PVC. SHUTTER SHOULD BE MADE OF 18MM. THICK POST FORMING PLYWOOD WITH MAGNET,LOCK & AUTO HINGES OF **HETTICH OR EQUIVALENT**.FILE RACK BASE MADE WITH LAMINATED PLY BOARD.INCLUDING ALL MATERIALS AND LABOUR ETC. COMPLETE AS PER SHOWN IN DETAILED DRAWING.				
81	**OVERHEAD FILE STORAGE**	**47.00**	**SFT**	**2,000.00**	**94,000.00**
	2400MM X 375MM X 900MM(H) - 2 PROVIDING AND FIXING THE HANGING FILE STORAGE FOR 18MM THICK (PLYWOOD BOARD) POST FORMING LAMINATED TOP WITH 6MM THICK PLYWOOD AT BACKSIDE FINISHED WITH 1MM. THICK APPROVED LAMINATE, MADE OUT OF **18MM THICK PLYWOOD WITH EXTERIOR SIDE 1MM. AND INTERIOR SIDE 0.6MM. APPROVED LAMINATE.** STORAGE UNIT BOX (MEASUREMENT SHOWN IN DRAWING) WITH WOODEN BEDDING PATTI/PVC. SHUTTER SHOULD BE MADE OF 18MM. THICK POST FORMING PLYWOOD WITH MAGNET, AUTO HINGES OF HETTICH OR EQUIVALENT. FOR HANGING THE FILE STORAGE FROM SLAB USED **25MMX25MM M.S SQUARE TUBE FRAMING** AS PER SHOWN IN DRAWING.INCLUDING ALL MATERIALS AND LABOUR ETC. COMPLETE AS PER SHOWN IN DETAILED DRAWING.				
82	**OVERHEAD FILE STORAGE**	**72.00**	**SFT**	**2,000.00**	**1,44,000.00**
	3700MM X 375MM X 900MM(H) - 2 PROVIDING AND FIXING THE HANGING FILE STORAGE FOR 18MM THICK (PLYWOOD BOARD) POST FORMING LAMINATED TOP WITH 6MM THICK PLYWOOD AT BACKSIDE FINISHED WITH 1MM. THICK APPROVED LAMINATE, MADE OUT OF **18MM THICK PLYWOOD WITH EXTERIOR SIDE 1MM. AND INTERIOR SIDE 0.6MM. APPROVED LAMINATE.** STORAGE UNIT BOX				

	(MEASUREMENT SHOWN IN DRAWING) WITH WOODEN BEDDING PATTI/PVC. SHUTTER SHOULD BE MADE OF 18MM. THICK POST FORMING PLYWOOD WITH MAGNET, AUTO HINGES OF HETTICH OR EQUIVALENT. FOR HANGING THE FILE STORAGE FROM SLAB USED **25MMX25MM M.S SQUARE TUBE FRAMING** AS PER SHOWN IN DRAWING.INCLUDING ALL MATERIALS AND LABOUR ETC. COMPLETE AS PER SHOWN IN DETAILED DRAWING.				
83	**FULL HEIGHT FILE STORAGE**	**69.00**	**SFT**	**2,000.00**	**1,38,000.00**
	3045MM X 400MM X 2100MM(H) PROVIDING AND FIXING THE FULL HEIGHT STORAGE FOR 18MM THICK (PLYWOOD BOARD) POST FORMING LAMINATED WITH 6MM THICK PLYWOOD AT BACKSIDE FINISHED WITH 1MM. THICK APPROVED LAMINATE, MADE OUT OF 18MM THICK PLYWOOD WITH EXTERIOR SIDE 1MM. AND INTERIOR SIDE 0.6MM. APPROVED LAMINATE. STORAGE UNIT BOX (MEASUREMENT SHOWN IN DRAWING) WITH WOODEN BEDDING PATTI/PVC. SHUTTER SHOULD BE MADE OF 18MM. THICK POST FORMING PLYWOOD WITH MAGNET,LOCK,AUTO HINGES OF HETTICH OR EQUIVALENT. INCLUDING ALL MATERIALS AND LABOUR ETC. COMPLETE AS PER SHOWN IN DETAILED DRAWING.				
84	**FULL HEIGHT FILE STORAGE**	**33.00**	**SFT**	**2,000.00**	**66,000.00**
	1420MM X 300MM X 2100MM(H) PROVIDING AND FIXING THE FULL HEIGHT STORAGE FOR 18MM THICK (PLYWOOD BOARD) POST FORMING LAMINATED WITH 6MM THICK PLYWOOD AT BACKSIDE FINISHED WITH 1MM. THICK APPROVED LAMINATE, MADE OUT OF **18MM THICK PLYWOOD WITH EXTERIOR SIDE 1MM. AND INTERIOR SIDE 0.6MM. APPROVED LAMINATE**. STORAGE UNIT BOX (MEASUREMENT SHOWN IN DRAWING) WITH WOODEN BEDDING PATTI/PVC. SHUTTER SHOULD BE MADE OF 18MM. THICK POST FORMING PLYWOOD WITH MAGNET,LOCK,**AUTO HINGES OF HETTICH OR EQUIVALENT**. INCLUDING ALL MATERIALS AND LABOUR ETC. COMPLETE AS PER SHOWN IN DETAILED DRAWING AND INSTRUCTIONS OF ENGINEER-IN-CHARGE.				
85	**PEON TABLES**	**3.00**	**NOS.**	**25,000.00**	**75,000.00**
	PROVIDING AND FIXING 1MM LAMINATED TOP & M.S POWDER COATED "O" FRAME LEGS.				
86	**PANTRY CABINET**	**37.00**	**SFT**	**2,500.00**	**92,500.00**
	PROVIDING AND FIXING PANTRY CABINET SIZE OF **1300MM X 675MM (H)** IS MADE WITH (BWR) PLY BOARD SHUTTER AND DRAWER,BOTH SIDE LAMINATE. MAGNET & AUTO HINGES FOR SHUTTER,TELESCOPIC CHANNELS OF HETTICH OR EQUIVALENT.OVERHEAD CABINET 1500MMX700MMX350MM OVERHEAD CABINET 1200MMX700MM(H)X300MM(D) MADE OUT OF 18MM THICK PLY BOARD EXTERIOR SIDE 1MM LAMINET AND INSIDE 0.6MM LAMINATE.SHUTTER SHOULD BE MADE OF 18MM THICK PLYWOOD WITH LAMINATE,WOODEN BEADING PATTI/PVC , MAGNET & **AUTO HINGES OF HETTICH OR EQUIVALENT**.INCLUDING ALL MATERIALS & LABOUR ETC.				
87	**PARTITION**	**370.00**	**SFT**	**1,400.00**	**5,18,000.00**
	PROVIDING AND FIXING PARTITION MADE WITH ALUMINUM FRAMING,BOTH SIDE 12MM THICK PLY,GROOVES,METAL STRIP				

	& PARTITION SURFACE IN LAMINATE(MAKE - CENTURY,MIKASA,GREENLAM **RS.1950 PER SHEET-8'X4').**				
88	**LOW PARTITION**	**50.00**	**SFT**	**1,400.00**	**70,000.00**
	PROVIDING AND FIXING PARTITION MADE WITH ALUMINUM FRAMING,BOTH SIDE 12MM THICK PLY,LAMINATE **(MAKE - CENTURY,MIKASA,GREENLAM RS.1950 PER SHEET-8'X4')** SURFACE 18MM THICK WOODEN PATTI ON TOP WITH 4MM GROOVE.				
89	**PALMET**	**60.00**	**SFT**	**700.00**	**42,000.00**
	PROVIDING & FIXING PALMET ABOVE ALL GLAZED WINDOWS WITH **18MM THICK PLY BOARD** WITH LAMINATE (**MAKE - CENTURY,MIKASA,GREENLAM RS.1950 PER SHEET-8'X4')** SURFACE.				
90	**WOODEN CEILING IN FOYER**	**20.00**	**SFT**	**800.00**	**16,000.00**
	PROVIDING AND FIXING PLY FRAMING BELOW AND COVERED WITH PLY,APPLYING VENEER (ABOUT RS.135/- PER SFT) ON PLY WITH GROOVES & MELAMINE POLISHED ON VENEER.				
91	**WAITING BENCH - 3 SEATER**	**1.00**	**NOS.**	**15,000.00**	**15,000.00**
	PROVIDING & FIXING 3SEATER POWDER COATED M.S BENCH WITH CUSHION SEATS, & PERFORATED SHEET BACK REST.				
	FIFTH FLOOR				
92	**OFFICER'S TABLE**	**1.00**	**NOS.**	**45,000.00**	**45,000.00**
	1500MM X 600MM X 750MM(H) PROVIDING & FIXING OFFICER'S TABLE TOP IN LAMINATED PLAY BOARD, M.S POWDER COATED "O" FRAME LEG ONE SIDE & OTHER SIDE LAMINATED PLY BOARD,WITH POWDER COATED KEY-BOARD TREY FIXED WITH M.S CLAMP.FRONT PANEL IN PLY BOARD WITH BOTH SIDE 1MM LAMINATE.				
93	**SIDE TABLE**	**1.00**	**NOS.**	**17,500.00**	**17,500.00**
	PROVIDING & FIXING TABLE SIZE OF 1100MM X 400MM X 750MM(H) ,TABLE TOP IN 1MM LAMINATE, DRAWER & SHUTTERS MADE FROM 18MM THICK PLY WITH MAGNET,MULTIPLE DRAWERS, LOCK AND TELESCOPIC CHANNEL FOR DRAWERS. **AUTO HINGES OF HETTICH OR EQUIVALENT.**				
94	**LOW HEIGHT FILE STORAGE**	**47.00**	**SFT**	**2,000.00**	**94,000.00**
	3600MM X 400MM X 1200MM(H) PROVIDING AND FIXING THE LOW HEIGHT STORAGE FOR 25MM THICK (PLYWOOD BOARD) POST FORMING LAMINATED TOP WITH 6MM THICK PLYWOOD AT BACKSIDE FINISHED WITH 1MM. THICK APPROVED LAMINATE, MADE OUT OF 18MM THICK PLYWOOD WITH EXTERIOR SIDE 1MM. AND INTERIOR SIDE 0.6MM. APPROVED LAMINATE. STORAGE UNIT BOX (MEASUREMENT SHOWN IN DRAWING) WITH WOODEN BEDDING PATTI/PVC. SHUTTER SHOULD BE MADE OF 18MM. THICK POST FORMING PLYWOOD WITH MAGNET,LOCK & **AUTO HINGES OF HETTICH OR EQUIVALENT**.FILE RACK BASE MADE WITH LAMINATED PLY BOARD.INCLUDING ALL MATERIALS AND LABOUR ETC. COMPLETE AS PER SHOWN IN DETAILED DRAWING.				
95	**LOW HEIGHT FILE STORAGE**	**20.00**	**SFT**	**2,000.00**	**40,000.00**

Signature and Stamp of Bidder

	1500MM X 400MM X 1200MM(H) PROVIDING AND FIXING THE LOW HEIGHT STORAGE FOR 25MM THICK (PLYWOOD BOARD) POST FORMING LAMINATED TOP WITH 6MM THICK PLYWOOD AT BACKSIDE FINISHED WITH 1MM. THICK APPROVED LAMINATE, MADE OUT OF 18MM THICK PLYWOOD WITH EXTERIOR SIDE 1MM. AND INTERIOR SIDE 0.6MM. APPROVED LAMINATE. STORAGE UNIT BOX (MEASUREMENT SHOWN IN DRAWING) WITH WOODEN BEDDING PATTI/PVC. SHUTTER SHOULD BE MADE OF 18MM. THICK POST FORMING PLYWOOD WITH MAGNET, LOCK & **AUTO HINGES OF HETTICH OR EQUIVALENT**.FILE RACK BASE MADE WITH LAMINATED PLY BOARD.INCLUDING ALL MATERIALS AND LABOUR ETC. COMPLETE AS PER SHOWN IN DETAILED DRAWING.				
96	**LOW HEIGHT FILE STORAGE**	**11.00**	**SFT**	**2,000.00**	**22,000.00**
	1350MM X 400MM X 750MM(H) PROVIDING AND FIXING THE LOW HEIGHT STORAGE FOR 25MM THICK (PLYWOOD BOARD) POST FORMING LAMINATED TOP WITH 6MM THICK PLYWOOD AT BACKSIDE FINISHED WITH 1MM. THICK APPROVED LAMINATE, MADE OUT OF 18MM THICK PLYWOOD WITH EXTERIOR SIDE 1MM. AND INTERIOR SIDE 0.6MM. APPROVED LAMINATE. STORAGE UNIT BOX (MEASUREMENT SHOWN IN DRAWING) WITH WOODEN BEDDING PATTI/PVC. SHUTTER SHOULD BE MADE OF 18MM. THICK POST FORMING PLYWOOD WITH MAGNET,LOCK & **AUTO HINGES OF HETTICH OR EQUIVALENT**.FILE RACK BASE MADE WITH LAMINATED PLY BOARD.INCLUDING ALL MATERIALS AND LABOUR ETC. COMPLETE AS PER SHOWN IN DETAILED DRAWING.				
97	**WORK STATION**	**2.00**	**NOS.**	**1,05,000.00**	**2,10,000.00**
	3700MM X 600MM X 750MM(H) PROVIDING & FIXING THE WORK STATION TABLE TOP 25MM THICK IN LAMINATE WITH MATCHING EDGE BANDING & ALUMINUM FLIP UP PROVISION.M.S POWDER COATED "O" FRAME LEGS,WIRE MANAGER TREY BELOW TABLE,POWDER COATED KEY-BOARD TREY FIXED WITH M.S CLAMPS. SEPARATE DRAWER UNIT - 400MM X 450MM(D) X 600MM(H) IN LAMINATED SURFACE, WITH LOCK & KEY, HANDLE AND TELESCOPIC CHANNEL OF **HETTICH OR EQUIVALENT.**				
98	**OVERHEAD FILE STORAGE**	**72.00**	**SFT**	**2,000.00**	**1,44,000.00**
	3700MM X 375MM X 900MM(H) - 2 PROVIDING AND FIXING THE HANGING FILE STORAGE FOR 18MM THICK (PLYWOOD BOARD) POST FORMING LAMINATED TOP WITH 6MM THICK PLYWOOD AT BACKSIDE FINISHED WITH 1MM. THICK APPROVED LAMINATE, MADE OUT OF 18MM THICK PLYWOOD WITH EXTERIOR SIDE 1MM. AND INTERIOR SIDE 0.6MM. APPROVED LAMINATE. STORAGE UNIT BOX (MEASUREMENT SHOWN IN DRAWING) WITH WOODEN BEDDING PATTI/PVC. SHUTTER SHOULD BE MADE OF 18MM. THICK POST FORMING PLYWOOD WITH MAGNET, **AUTO HINGES OF HETTICH OR EQUIVALENT**. FOR HANGING THE FILE STORAGE FROM SLAB USED 25MMX25MM M.S SQUARE TUBE FRAMING AS PER SHOWN IN DRAWING.INCLUDING ALL				

	MATERIALS AND LABOUR ETC. COMPLETE AS PER SHOWN IN DETAILED DRAWING.				
99	**FULL HEIGHT FILE STORAGE**	**69.00**	**SFT**	**2,000.00**	**1,38,000.00**
	3045MM X 400MM X 2100MM(H) PROVIDING AND FIXING THE FULL HEIGHT STORAGE FOR 18MM THICK (PLYWOOD BOARD) POST FORMING LAMINATED WITH 6MM THICK PLYWOOD AT BACKSIDE FINISHED WITH 1MM. THICK APPROVED LAMINATE, MADE OUT OF 18MM THICK PLYWOOD WITH EXTERIOR SIDE 1MM. AND INTERIOR SIDE 0.6MM. APPROVED LAMINATE. STORAGE UNIT BOX (MEASUREMENT SHOWN IN DRAWING) WITH WOODEN BEDDING PATTI/PVC. SHUTTER SHOULD BE MADE OF 18MM. THICK POST FORMING PLYWOOD WITH MAGNET, LOCK, AUTO HINGES OF HETTICH OR EQUIVALENT. INCLUDING ALL MATERIALS AND LABOUR ETC. COMPLETE AS PER SHOWN IN DETAILED DRAWING.				
100	**FULL HEIGHT FILE STORAGE**	**33.00**	**SFT**	**2,000.00**	**66,000.00**
	1420MM X 300MM X 2100MM(H) PROVIDING AND FIXING THE FULL HEIGHT STORAGE FOR 18MM THICK (PLYWOOD BOARD) POST FORMING LAMINATED WITH 6MM THICK PLYWOOD AT BACKSIDE FINISHED WITH 1MM. THICK APPROVED LAMINATE, MADE OUT OF 18MM THICK PLYWOOD WITH EXTERIOR SIDE 1MM. AND INTERIOR SIDE 0.6MM. APPROVED LAMINATE. STORAGE UNIT BOX (MEASUREMENT SHOWN IN DRAWING) WITH WOODEN BEDDING PATTI/PVC. SHUTTER SHOULD BE MADE OF 18MM. THICK POST FORMING PLYWOOD WITH MAGNET, LOCK, AUTO **HINGES OF HETTICH OR EQUIVALENT**. INCLUDING ALL MATERIALS AND LABOUR ETC. COMPLETE AS PER SHOWN IN DETAILED DRAWING.				
101	**WOODEN CEILING IN FOYER**	**20.00**	**SFT**	**800.00**	**16,000.00**
	PROVIDING AND FIXING PLY FRAMING BELOW AND COVERED WITH PLY,APPLYING VENEER (ABOUT **RS.135/- PER SFT**) ON PLY WITH GROOVES & MELAMINE POLISHED ON VENEER.				
102	**PANTRY CABINET**	**37.00**	**SFT**	**2,500.00**	**92,500.00**
	PROVIDING AND FIXING PANTRY CABINET SIZE OF **1455MM X 675MM (H)** IS MADE WITH (BWR) PLY BOARD SHUTTER AND DRAWER, BOTH SIDE LAMINATE. MAGNET & **AUTO HINGES FOR SHUTTER, TELESCOPIC CHANNELS OF HETTICH OR EQUIVALENT.** OVERHEAD CABINET **1400MMX700MM(H)X300MM(D)** MADE OUT OF 18MM THICK PLY BOARD EXTERIOR SIDE 1MM LAMINET AND INSIDE 0.6MM LAMINATE.SHUTTER SHOULD BE MADE OF 18MM THICK PLYWOOD WITH LAMINATE,WOODEN BEADING PATTI/PVC , MAGNET & **AUTO HINGES OF HETTICH OR EQUIVALENT**.INCLUDING ALL MATERIALS & LABOUR ETC.				
103	**PARTITION**	**450.00**	**SFT**	**1,400.00**	**6,30,000.00**
	PROVIDING AND FIXING PARTITION MADE WITH ALUMINUM FRAMING, BOTH SIDE 12MM THICK PLY, GROOVES, METAL STRIP & PARTITION SURFACE IN LAMINATE (MAKE - CENTURY, MIKASA, GREENLAM RS.1950 PER SHEET-8'X4').				
104	**PALMET**	**63.00**	**SFT**	**700.00**	**44,100.00**
	PROVIDING & FIXING PALMET ABOVE ALL GLAZED WINDOWS				

	WITH 18MM THICK PLY BOARD WITH LAMINATE (MAKE - **CENTURY,MIKASA,GREENLAM RS.1950 PER SHEET-8'X4'**)SURFACE.				
105	**PEON TABLE**	**1.00**	**NOS.**	**25,000.00**	**25,000.00**
	800MM X 500MM X 750MM(H) PROVIDING AND FIXING 1MM LAMINATED TOP & M.S POWDER COATED "O" FRAME LEGS.				
106	**WAITING BENCH - 3 SEATER**	**1.00**	**NOS.**	**15,000.00**	**15,000.00**
	PROVIDING & FIXING 3SEATER POWDER COATED M.S BENCH WITH CUSHION SEATS, & PERFORATED SHEET BACK REST.				
	SIXTH FLOOR				
107	**PANTRY CABINET**	**38.00**	**SFT**	**2,500.00**	**95,000.00**
	PROVIDING AND FIXING PANTRY CABINET SIZE OF **1705MM X 675MM (H**) IS MADE WITH (BWR) PLY BOARD SHUTTER AND DRAWER, BOTH SIDE LAMINATE. MAGNET & **AUTO HINGES FOR SHUTTER, TELESCOPIC CHANNELS OF HETTICH OR EQUIVALENT.** OVERHEAD CABINET **1400MMX700MM(H)X300MM(D)** MADE OUT OF 18MM THICK PLY BOARD EXTERIOR SIDE 1MM LAMINET AND INSIDE 0.6MM LAMINATE.SHUTTER SHOULD BE MADE OF 18MM THICK PLYWOOD WITH LAMINATE, WOODEN BEADING PATT I /PVC, **MAGNET & AUTO HINGES OF HETTICH OR EQUIVALENT**.INCLUDING ALL MATERIALS & LABOUR ETC.				
108	**WOODEN CEILING IN HALL**	**200.00**	**SFT**	**800.00**	**1,60,000.00**
	PROVIDING AND FIXING PLY FRAMING BELOW AND COVERED WITH PLY,APPLYING VENEER (ABOUT RS.135/- PER SFT) ON PLY WITH GROOVES & MELAMINE POLISHED ON VENEER.				
109	**WOODEN CEILING IN FOYER**	**20.00**	**SFT**	**800.00**	**16,000.00**
	PROVIDING AND FIXING PLY FRAMING BELOW AND COVERED WITH PLY,APPLYING VENEER (ABOUT RS.135/- PER SFT) ON PLY WITH GROOVES & MELAMINE POLISHED ON VENEER.				
110	**GRID CEILING**	**380.00**	**SFT**	**125.00**	**47,500.00**
	PROVIDING & FIXING G.I. SECTION BELOW AND COVERED WITH LIGHT WEIGHT 600 x 600 CEILING TILES.				
111	**PARTITION**	**220.00**	**SFT**	**1,400.00**	**3,08,000.00**
	PROVIDING AND FIXING PARTITION MADE WITH ALUMINUM FRAMING,BOTH SIDE 12MM THICK PLY,GROOVES,METAL STRIP & PARTITION SURFACE IN LAMINATE **(MAKE - CENTURY, MIKASA, GREENLAM RS.1950 PER SHEET - 8'X4').**				
112	**PALMET**	**63.00**	**SFT**	**700.00**	**44,100.00**
	PROVIDING & FIXING PALMET ABOVE ALL GLAZED WINDOWS WITH 18MM THICK PLY BOARD WITH LAMINATE (**MAKE - CENTURY,MIKASA,GREENLAM RS.1950 PER SHEET-8'X4')**SURFACE.				
113	**STAGE TABLE PODIUM**	**150.00**	**SFT**	**1,000.00**	**1,50,000.00**
	PROVIDING & FIXING THE PODIUM STAGE WITH 18MM PLY BOARD ON M.S FRAMING HEIGHT OF 200MM & APPROVED Signature and Stamp of Bidder				

	12MM THICK WOODEN FLOOR.				
114	**PODIUM**	**1.00**	**NOS.**	**10,000.00**	**10,000.00**
	PROVIDING & FIXING THE PODIUM WITH 18MM PLY BOARD WITH LAMINATE.				
115	**GUEST TABLE**	**2.00**	**NOS.**	**15,000.00**	**30,000.00**
	PROVIDING & FIXING TABLE SIZE OF 1350MM X 600MM X 750MM(H) , WITH "O" FRAMED METAL LEGS,AND LAMINATED TABLE TOP.				
116	**PRESENTATION PC TABLE**	**1.00**	**NOS.**	**15,000.00**	**15,000.00**
	PROVIDING & FIXING TABLE SIZE OF 1200MM X 600MM X 750MM(H) ,TABLE TOP IN 1MM LAMINATE, DRAWER & SHUTTERS MADE FROM 18MM THICK PLY WITH MAGNET,MULTIPLE DRAWERS, LOCK AND TELESCOPIC CHANNEL FOR DRAWERS.AUTO HINGES OF HETTICH OR EQUIVALENT.				
117	**GLASS DOOR**	**35.00**	**SFT**	**650.00**	**22,750.00**
	1350MM X 2375MM PROVIDING & FIXING 12MM THICK TOUGHEN GLASS,ON FLOORSPRING,WITH S.S HANDLE.				
	CHAIRS				
118	**CHAIRMAN'S CHAIR (MAKE - HOF,FEATHERLITE) AS PER INTERIOR**	**1.00**	**NOS.**	**87,000.00**	**87,000.00**
119	**CHAIRMAN'S VISITORS CHAIR (MAKE - HOF,FEATHERLITE) AS PER INTERIOR**	**3.00**	**NOS.**	**25,000.00**	**75,000.00**
120	**F.F - RECEPTION CHAIR AS PER INTERIOR**	**1.00**	**NOS.**	**7,500.00**	**7,500.00**
121	**G.M & AGM'S CHAIR AS PER INTERIOR**	**6.00**	**NOS.**	**20,000.00**	**1,20,000.00**
122	**VISITORS CHAIR AS PER INTERIOR**	**13.00**	**NOS.**	**10,000.00**	**1,30,000.00**
123	**OFFICER'S & STAFF CHAIRS AS PER INTERIOR**	**44.00**	**NOS.**	**7,500.00**	**3,30,000.00**
124	**PEON'S CHAIR AS PER INTERIOR**	**8.00**	**NOS.**	**5,000.00**	**40,000.00**
125	**FOYER ARM CHAIRS - 1ST & 6TH FLOOR AS PER INTERIOR**	**4.00**	**NOS.**	**10,000.00**	**40,000.00**
126	**GUEST CHAIRS AS PER INTERIOR**	**4.00**	**NOS.**	**20,000.00**	**80,000.00**
127	**MEMBERS CHAIR AS PER INTERIOR**	**53.00**	**NOS.**	**7,000.00**	**3,71,000.00**
128	**CONFERANCE CHAIRS AS PER INTERIOR**	**7.00**	**NOS.**	**25,000.00**	**1,75,000.00**
	CURTAINS				
129	**1ST FLOOR CURTAIN (MAKE - ASIAN PAINT) MOTORISED HONEYCOMB BLACK OUT CURTAIN.**	**532.00**	**SFT**	**1,500.00**	**7,98,000.00**
130	**2ND FLOOR CURTAIN (MAKE - ASIAN PAINT POLY VINYL FABRIC) ROLLER BLIND , BLACK OUT & MANUALY OPERABLE CURTAIN.**	**560.00**	**SFT**	**350.00**	**1,96,000.00**
131	**3RD FLOOR CURTAIN (MAKE - ASIAN PAINT POLY VINYL FABRIC) ROLLER BLIND , BLACK OUT & MANUALY OPERABLE CURTAIN.**	**560.00**	**SFT**	**350.00**	**1,96,000.00**
132	**4TH FLOOR CURTAIN (MAKE - ASIAN PAINT POLY VINYL FABRIC)**	**560.00**	**SFT**	**350.00**	**1,96,000.00**

	ROLLER BLIND , BLACK OUT & MANUALY OPERABLE CURTAIN.				
133	**5TH FLOOR CURTAIN (MAKE - ASIAN PAINT POLY VINYL FABRIC)** **ROLLER BLIND , BLACK OUT & MANUALY OPERABLE CURTAIN.**	**560.00**	**SFT**	**350.00**	**1,96,000.00**
134	**6TH FLOOR CURTAIN (MAKE - ASIAN PAINT POLY VINYL FABRIC)** **ROLLER BLIND , BLACK OUT & MANUALY OPERABLE CURTAIN.**	**560.00**	**SFT**	**350.00**	**1,96,000.00**
	PART-B FURNITURE WORK TOTAL RS.				**1,50,85,000.00**

Signature and Stamp of Bidder

THE AHMEDABAD DISTRICT CO-OPERATIVE BANK LTD.

SCHEDULE-B

PART-C ELECTRICAL WORKS

NAME OF WORK- ELECTRICAL WORKS AT- NEW OFFICE BUILDING, AHMEDABAD

No	ITEMS	QTY	UNIT	RATE RS.	TOTAL RS.
	PART - 1 - INTERNAL WIRING				
	"WITH MODULAR TYPE SWITCHES **Wiring of points to be done in concealed / Open manner (As per drawings provided) in 25 mm dia medium guage Rigid PVC FRLS pipe. Wiring shall be done with FRLS type copper flexible wire of 650V/1100V. Separate pipe should be taken for circuit mains. Nos of ciruit of the same phases may be taken in same conduit (maximum 2 ckts).The circuit shall be laid in 25/40 mm dia medium guage rigid PVC FRLS pipe.The point rate shall include all the necessary piping and wiring from sub panel / Distribution board to switch board & switch board to the batten holder / angle holder / connector / ceiling rose all inclusive except sub panel / Dist board."**				
	"The wiring shall be done as per relevant prevailing standard. The looping of the wiring should be done in the switch boxes or light and fan point outlet boxes to avoid the junction boxes. The junction boxes and switch boxes for the ceiling light point, fan point etc shall be minimum 60mm deep. All the necessary jarry in brick plastered walls should be done with machine cutter only, also jarry should be filled with cement, sand and wire mesh as required, the material cost for rough finish shall be included in point rate.Whenever pipes are required to be laid in flooring shall be of heavy guage (HMS). Wiring should be done as per distribtion details. Each circuit should have dedicated phase, neutral & earth wire. Wire sizes to be used as under where ever open conduiting is to be done, the required clamps etc accessories shall be included in the items here POINT RATE INCLUD FROM DB TO SB TO POINT OUT LAT (NO EXTRA MAIN FOR POINT WIRING) **For Light Points /fan point/ wall fan / 6A 3 Pin Plug** **0 SB to SB 0 2.5sqmm for Phase & Neutral & 1.5 sqmm for Earth** **0 SB to Point 0 1.5 sqmm for Phase & Neutral & Earth** **For 6A Plug point.0 1.5 sqmm for Phase, Neutral & Earth** **For 6/10/16A general purpose plug point0 2.5 sqmm for Phase, Neutral & 1.5 sqmm Earth A/C** **For 16A Geyser0 4 Sqmm for Phase, Neutral & 2.5 sqmm Earth** **For 20/32A plug point 0 6 sqmm for Phases, Neutral & 4 sqmm Earth** **For Concealed wiring no zarry will be allowed in expose brick / Finish wall / precast wall. The conduit shall be provided when the walls are under construction. The pipes in slab shall be laid before the precast slab is casted."**				
	Average Circuit length from SB to Primary point : 10 Mtr. & from Primary point to Secondary point : 5 Mtr.				
	"DIRECT FROM MCBs **Wiring of points to be done in Aluminium Hollow Pipe using (3c x 2.5sqmm) FRLS unarmo0ed cu cable as per detail provided (with out cost of MCB) for Basement Wiring. The point rate shall include all the necessary**				

	supports for cabling, required junction boxes at fixt0es to terminate the cable & providing & installing cable & flexible tails to the fixt0es from the JBs in complete manner. without cost of MCB"				
	"The wiring shall be done as per relevant prevailing standard. The junction boxes for the points shall be minimum 75 deep. Cable sizes to be used as under For Light Points /fan point/ wall fan / 6A 3 Pin Plug 0 MCB to Point 0 (2Cx2.5 sqmm + 1cx1.5 sqmm.) For 6/10/16A general p0pose plug point0 2.5 sqmm for Phase, Neutral & 1.5 sqmm Earth For 20/32A plug point0 6 sqmm for Phases, Neutral & 6 sqmm Earth"				
1.1	"Average Length LDB to Primary point : 8 Mtr. & from Primary point to Secondary point : 5 Mtr.				
1.1.1	One light point controlled by one single way 5 A switch.	128.00	NOS.	1,150.00	1,47,200.00
1.1.2	-do- as 1.1 but looped from above.	151.00	NOS.	575.00	86,825.00
1.1.3	One light point controlled by two way 5 A switch.	7.00	NOS.	1,650.00	11,550.00
1.1.4	-do- as 1.1 but looped from above.	7.00	NOS.	825.00	5,775.00
1.1.5	One Bell point controlled by one single way bell push 5 A switch.	11.00	NOS.	1,500.00	16,500.00
1.1.6	One fan outlet point controlled by one 5 A switch and step type electonic regulator.	5.00	NOS.	1,500.00	7,500.00
1.1.7	One Ext fan outlet point controlled by one 5 A switch	13.00	NOS.	1,500.00	19,500.00
1.1.8	One 6 A x 5 pin 230 Volt socket outlet point controlled by one 5 A switch located on switch board.	94.00	NOS.	775.00	72,850.00
1.1.9	6 A x 5 pin switched socket outlet point at convenient location with 2X2.5 + 1X1.5 sq mm ckt wiring from D.B.	37.00	NOS.	1,150.00	42,550.00
1.1.10	5/15 A x 230 Volt switched socket outlet point for appliances/peripherals to be done with 2.5 sq mm ckt from D.B..	15.00	NOS.	2,300.00	34,500.00
1.1.11	5/15 A x 230 Volt switched socket outlet point for appliances/peripherals to be done with 4.0 sq mm ckt from D.B..	5.00	NOS.	3,350.00	16,750.00
1.1.12	2 nos 6 A x 5 pin switched socket outlet point with 1 nos 16 A switch with 2X2.5 +1X1.5 sq mm ckt wiring from D.B.	134.00	NOS.	1,900.00	2,54,600.00
1.1.13	ITC of 6A socket with box and plate complete - For HVAC VRV indoor unit to be done with 2.5 sq mm wire from D.B.	NOS.		-	-
1.1.14	T.V.Out lat Only	4.00	NOS.	600.00	2,400.00
1.1.15	Laying of 25 mm dia. rigid PVC conduit of medium guage with all accessories complete.	492.00	RFT	27.44	13,500.48
1.1.16	Elevator Shaft Lighting			-	
	SITC of elevator shaft light points using 3C x 2.5 sq. mm cu arm Cable from lift panel PVC insulated multi strand flexible copper conductors in 25mm dia PVC conduit for a set of 7 set of 1 light points control from sb with 5 amp plug point.The rate shall include cost of 7Nos. of Bulk head fittings with wire guard mesh necessary fixing accessories 1 nos Two way Light control point.	0	NOS.	0.00	0.00
1.2	MAINS : -Only from From D.B. to D.B. / industrial sockets / VRV IDU for rooms only.			-	
1.2.1	Drawing mains with 2 nos. of 2.5 sq mm Cu. PVC insulated flexible wire with ISI and FIA approval for 650 V/ 1100 V and 1 nos 1.5 sqmm Cu. PVC insulated flexible wires with ISI approval for 650 V/ 1100 V as earth wires to be drawn in 25 mm diameter rigid PVC conduit of medium guage having ISI amd FIA approval with all necessary accessories.	656.00	RFT	57.93	38,002.08
1.2.2	Drawing mains with 2 nos. of 4 sq mm Cu. PVC insulated flexible wire with ISI and FIA approval for 650 V/ 1100 V and 1 nos 2.5 sqmm Cu. PVC insulated	164.00	RFT	102.74	16,849.36

	flexible wires with ISI approval for 650 V/ 1100 V as earth wires to be drawn in 25 mm diameter rigid PVC conduit of medium guage having ISI amd FIA approval with all necessary accessories.				
1.2.3	**Drawing mains with 4 nos. of 6 sq mm Cu. PVC insulated flexible wire with ISI and FIA approval for 650 V/ 1100 V and 2 nos 4 sqmm Cu. PVC insulated flexible wires with ISI approval for 650 V/ 1100 V as earth wires to be drawn in 25 mm diameter rigid PVC conduit of medium guage having ISI amd FIA approval with all necessary accessories -**	**82.00**	**RFT**	**275.91**	**22,624.62**
1.2.4	**Drawing mains with 4 nos. of 10 sq mm Cu. PVC insulated flexible wire with ISI and FIA approval for 650 V/ 1100 V and 2 nos 6 sqmm Cu. PVC insulated flexible wires with ISI approval for 650 V/ 1100 V as earth wires to be drawn in 25 mm diameter rigid PVC conduit of medium guage having ISI amd FIA approval with all necessary accessories -**	**98.40**	**RFT**	**438.72**	**43,170.05**
1.2.5	**Drawing mains with 4 nos. of 16 sq mm Cu. PVC insulated flexible wire with ISI and FIA approval for 650 V/ 1100 V and 2 nos 6 sqmm Cu. PVC insulated flexible wires with ISI approval for 650 V/ 1100 V as earth wires to be drawn in 25 mm diameter rigid PVC conduit of medium guage having ISI amd FIA approval with all necessary accessories -**	**98.40**	**RFT**	**619.51**	**60,959.78**
	PART - 2 - INSTALLATION OF FIXTURES				
	Installation, testing and commissioning reputed make following lighting fixture / fans with supply of hardwares and accessories complete In all respect as per drawing, as per specification and as per direction of engineer incharge.				
2.1	**1200 DIA CEILING FAN**	**5.00**	**NOS.**	**2,800.00**	**14,000.00**
2.2	**EXHAUST FAN FOR TOILETS**	**13.00**	**NOS.**	**2,400.00**	**31,200.00**
2.3	**BELL POINT**	**11.00**	**NOS.**	**300.00**	**3,300.00**
2.4	**Celest Arch Downlight – 4K – 15W – Trim less**	**28.00**	**NOS.**	**11,250.00**	**3,15,000.00**
2.5	**Celest Arch Downlight – 4K – 8W – Trim less**	**4.00**	**NOS.**	**8,625.00**	**34,500.00**
2.6	**Emina Pro COB Downlight – 4K – 15W**	**158.00**	**NOS.**	**1,305.00**	**2,06,190.00**
2.7	**Emina Pro COB Downlight – 4K – 8W**	**31.00**	**NOS.**	**1,280.00**	**39,680.00**
2.8	**Magnetic track slim**	**44.00**	**MTR**	**2,080.00**	**91,520.00**
2.9	**Magnetic track fixed jointer**	**20.00**	**NOS.**	**680.00**	**13,600.00**
2.10	**Magnetic track I shaped connector**	**20.00**	**NOS.**	**250.00**	**5,000.00**
2.11	**LED Orelli Slim round – 7W**	**53.00**	**NOS.**	**1,715.00**	**90,895.00**
2.12	**LED insta ray slim led fixed – 12W**	**71.00**	**NOS.**	**1,715.00**	**1,21,765.00**
2.13	**Linear hanging profile 45W – 2000X50X80**	**2.00**	**NOS.**	**9,695.00**	**19,390.00**
2.14	**Linear hanging profile 38W – 1800X50X80**	**1.00**	**NOS.**	**7,325.00**	**7,325.00**
2.15	**Linear hanging profile 25W – 1200X50X80**	**8.00**	**NOS.**	**4,840.00**	**38,720.00**
	PART - 3 - MISCELLANEOUS ITEMS				
3.1	**SITC of 32 mm PVC pipe of heavy gauge with bends / couplers etc complete with accessories to mount the same within shaft / suspend with help of threaded rod / slotted angle from ceiling etc complete.**	**492.00**	**RFT**	**13.72**	**6,750.24**

3.2	-do as above but 40 mm dia.	164.00	RFT	16.77	2,750.28
3.3	-do as above but 50 mm dia.		RFT	-	-
3.4	-do- as above bu 100 mm dia.		RFT	-	-
3.5	SITC of IP 65 PVC boxes suitable for housing 40A - 4-6 way connectors for external area cable input - output near each fixture.	-	NOS.	-	-
3.6	SITC of IP 65 category 300 X 300 PVC type junction boxes with necessary loop in loop out connectors / busbars / internal wiring if required etc. complete. The boxes if required shall be mounted on 9" MS supports which shall be considered in cost.	-	NOS.	-	-
	ELV SYSTEM				
	PART – 4 - TELEPHONE /DATA NETWORKING SYSTEM				
4.1	Supply and Installation Testing and Commissoning of approved make RJ11 Telephone Socket and making connection as per drawing and as per direction of engineer incharge.(accessories only)	45.00	NOS.	550.00	24,750.00
4.2	Supply and Installation Testing and Commissoning of approved make computer point and making connection RJ45 Computer Socket as per drawing and as per direction of engineer incharge.(accessories only)	114.00	NOS.	950.00	1,08,300.00
4.3	SITC of Cat 6 E wire (Gray Colour) for Voice Networking as per standard specifications and directions of Engineer-in-charge.	5,002.00	RFT	38.00	1,90,076.00
4.4	SITC of Cat 6 E wire (Blue Colour) for Data Networking as per standard specifications and directions of Engineer-in-charge.	13,007.00	RFT	38.00	4,94,266.00
4.5	Supply, Laying of 12 pair SINGLE MODE fibre optic cable in ready made trench / cable trays, fixed on wall / structure including supply and fixing of 25mm wide 2mm thick Aluminium clamps, GI Saddle / Spacers, Aluminium cable identification Tags at both the ends, cleats spares, hardware, inlcuding dressing of cables etc.	724.88	RFT	64.02	46,406.82
4.6	Terminaiton of above fiber optic cable with supplying all necessary accessories, LIU ETC, completed in all respect.	1.00	LOT	30,000.00	30,000.00
4.7	Supply and installation of Medium duty 25 mm Dia PVC MMS conduits in a surface / concealed manner of following sizes including all hardwares, junction boxes etc, as per standard specifications and directions of Engineer-in-charge.	6,560.00	RFT	27.44	1,80,006.40
	PART - 5 - CCTV SYSTEM				
5.1	SITC of Cat 6 E wire (Yellow Colour) for CCTV Networking as per standard specifications and directions of Engineer-in-charge.	7,002.80	RFT	38.00	2,66,106.40
5.2	Supply and installation of Medium duty 25 mm Dia PVC MMS conduits in a surface / concealed manner of following sizes including all hardwares, junction boxes etc, as per standard specifications and directions of Engineer-in-charge.	3,476.80	RFT	27.44	95,403.39
	PART -6 - PA SYSTEM				
6	2 Core 1.5 Sqmm Armoured Screened Sheilded Speaker Wire	3,444.00	RFT	76.22	2,62,501.68
	PART - 7 - TV SYSTEM				
7.1	SITC of RG6 wire for TV as per standard specifications and directions of Engineer-in-charge. Signature and Stamp of Bidder	95.00	EA	110.00	10,450.00

7.2	**Supply and installation of Medium duty 25 mm Dia PVC MMS conduits in a surface / concealed manner of following sizes including all hardwares, junction boxes etc, as per standard specifications and directions of Engineer-in-charge.**	**311.60**	**RFT**	**27.44**	**8,550.30**
	PART - 8 - EMS SYSTEM				
8.1	**Supply, Laying & Termination of 2 Core 1.5 Sqmm Belden Cable including supply of weatherproof double compression type cable glands and tinned copper lugs, including cutting / stripping of cable insulation, Installation, testing and commissioning of cable glands, crimping of the cable cores, marking with wire number ferrules, etc., including all labour and materials, as per standard specifications and directions of 'Engineer-in-charge.**	**492.00**	**RFT**	**114.33**	**56,250.36**
8.2	**Supply and installation of Medium duty 25 mm Dia PVC MMS conduits in a surface / concealed manner of following sizes including all hardwares, junction boxes etc, as per standard specifications and directions of Engineer-in-charge.**	**246.00**	**RFT**	**27.44**	**6,750.24**
8.3	**Supply and installation of 25 mm dia flexible PVC conduits as per standard specifications and directions of Engineer-in-charge.**	**65.60**	**RFT**	**15.24**	**1,000.00**
				PART-C ELECTRICAL WORKS TOTAL RS.	**37,36,009.23**

Signature and Stamp of Bidder

THE AHMEDABAD DISTRICT CO-OPERATIVE BANK LTD.					
SCHEDULE-B					
PART D (AIR CONDITIONING WORKS)					
NAME OF WORK - AIR CONDITIONING WORKS AT- NEW OFFICE BUILDING, AHMEDABAD					
SR NO.	**DESCRIPTION OF WORKS**	**QTY**	**UNIT**	**RATE RS.**	**TOTAL RS.**
	Supply, Installation, Testing & Commissioning of High Side Work VRV/VRF				
1	**Supply, Installation, Testing, Commissioning of Floor mounted Top / Side discharge : Cooling type Outdoor unit with Variable Refrigerant Flow / Volume system of 100% inverter type scroll compressors with refrigerant piping, refnet connection, individual controller, Necessary integrator for BMS with open protocol. The quote for the work should include necessary, lifting & shifting charges for mounting the Condensing units with MS stand & rubber pads, first charge of 410A refrigerant and mounting of indoor units and other accessories. (If Top Discharge Oudoor Unit shall not install directly in ambient than GI Exhaust cowl with SS birdscreen shall require & Cowl design shall be as per the OEM recommandation). Where Marked in Drawing or Required as per Site Condition etc complete as required by Client / Consultant / E-I-C. (Cooling Only)**				
1.1	**08 HP (1st,2nd ,4th & 5th Floor Outdoor Unit's)**	**4.00**	**NOS.**	**2,95,010.54**	**11,80,042.16**
1.2	**10 HP (3rd & 6th Floor Unit's)**	**2.00**	**NOS.**	**3,07,691.90**	**6,15,383.80**
2	**Supply, Installation, Testing, Commissioning of 4 Way type Cassette Indoor unit with Fan coil consisting of 3/4 row-cooling coil blower with motor, filters, drain pan & casing.The indoor unit shall be suitable for a power supply of 240V/ 1 phase/ 50Hz with corded/cordless remote. The unit shall be BMS compatible & complete as required by Client / Consultant / E-I-C.**				
2.1	**1.5 TR / 620/800CFM**	**2.00**	**NOS.**	**43,459.82**	**86,919.64**
2.2	**2.5 TR / 830CFM**	**4.00**	**NOS.**	**50,238.25**	**2,00,953.00**
2.3	**3.0 TR / 1165CFM**	**5.00**	**NOS.**	**51,338.29**	**2,56,691.45**
3	**Supply, Installation, Testing, Commissioning of 1 Way type Cassette Indoor unit with Fan coil consisting of 3/4 row-cooling coil blower with motor, filters, drain pan & casing.The indoor unit shall be suitable for a power supply of 240V/ 1 phase/ 50Hz with corded/cordless remote. The unit shall be BMS compatible & complete as required by Client / Consultant / E-I-C.**				
3.1	**2.0 TR / 530**	**4.00**	**NOS.**	**48,865.26**	**1,95,461.04**
4	**Supply, Installation, Testing, Commissioning of Split unit type Indoor unit with Fan coil consisting of 3/4 row-cooling coil, blower with motor, filters, drain pan & casing. The indoor unit shall be suitable for a power supply of 240V/ 1 phase/ 50Hz with cordless remote. The unit shall be BMS compatible & complete as required by Client / Consultant / E-I-C.**				
4.1	**1.0 TR / 300CFM**	**2.00**	**NOS.**	**20,836.90**	**41,673.80**
4.2	**1.28 TR / 424CFM**	**2.00**	**NOS.**	**21,358.08**	**42,716.16**
4.3	**1.6 TR / 800CFM**	**2.00**	**NOS.**	**22,922.65**	**45,845.30**

Signature and Stamp of Bidder

5	**Supply, Installation, Testing, Commissioning of 3 Star rated Inverter type Split unit (DX Type) Indoor unit with fan coil consisting of 3/4 row-cooling coil blower with motor, filters, drain pan & casing. The indoor unit shall be suitable for a power supply of 240V/ 1 phase/ 50Hz with cordless remote.complete as required by Client / Consultant / E-I-C.**				
5.1	**1.0 TR**	**2.00**	**NOS.**	**38,559.08**	**77,118.16**
	Note : Review the HVAC drawing and, if required for proper drainage, add a drain pump				
6	**Supply, Installation, Testing, Commissioning of Basic Central Remote Controller for VRF System for connecting all IDUS with ODU as mentioned below.**	**1.00**	**NOS.**	**72,227.72**	**72,227.72**
	Corded Remote Controllers				
	Zone wise Centralized Remote Controller				
	Central Control Monitor For Entire System.				
	Central Remote Controller for above system comprising of all required Software. PC will be supplied by client. System should control & monitor all installed IDU / ODU. Following should be minimum controlling & monitoring features that system should cover; Start / Stop, Temperature settings, Mode control, Group formation, view alarms, Fault Diagnosis.				
7	**Supply, Installation, Testing, Commissioning of "Y" Joints.**				
7.1	**Outdoor Joints**	**0**	**NOS.**		
7.2	**Indoor Joints**	**15.00**	**NOS.**	**4,652.51**	**69,787.65**
8	**Refrigerant Piping**				
	Supply, Installation, Testing & Commissioning of One circuit refrigerant rigid piping for VRF System of minimum 18G between indoor & outdoor unit. High pressure copper refrigerant piping including R410a refrigerant of suitable size as required and duly insulated with 19mm thick nitrile insulation with class 'O' fire retardant & anti microbial, anti fungal properties in tubing form. Entire refrigerant piping work shall be carried out in accordance with the specifications. MS sleeves of requisite size shall be provided at wall crossing.				
8.1	**Piping inside occupied spaces shall be supported using MS hangers duly painted with black enamel paint. Internal Refrigerant piping in exposed ceiling area shall be laid on perforated type cable trays without cover.**	**426.40**	**RFT**	**787.96**	**3,35,986.14**
8.2	**External Refrigerant piping shall be laid on GI covered perforated type cable trays. Cable trays used for external refrigerant piping shall be covered with GI cover. Quoted price shall be inclusive of necessary glass cloth and minimum two layers of UV protection paint to be applied over insulation for all exposed pipes of approved make with necessary accessories etc complete as required by Client / Consultant / E-I-C. Piping shall be of following sizes :**	**65.60**	**RFT**	**949.30**	**62,274.00**
8.3	**Topping up refrigerant for complete system having total refrigerant piping length is for Suction & Discharge circuit shall be considered.**	**1.00**	**Lot**	**55,098.82**	**55,098.82**

Signature and Stamp of Bidder

9	**Supply and Erecting of perforated type Hot dip G.I.cable tray for Internal refrigerant piping in exposed ceiling & External refrigerant piping of 16G of specific dimensions. The cable tray shall be hung from ceiling / fixed to wall/rest on floor with necessary ceiling suspendors/supports from floors along with necessary accessories. Should be included in cost. The tray shall be earthed. Min size (not a limitation) of supports shall be as follows (a).-up to 300mm tray 2nos. 8mm full threaded G.i. rod with 2nos.anchor fastener and "C" channel support at 500mm distance (b) 450 to 600mm tray 2nos.10mm full treaded G.I. rodwith 2nos. anchor fastener and "C" channel support at 500mm distance (c) 750 / 1000 mm cable tray with fabrication of 25 x 6 or 50 x 3 mm angle frame with min. 4 nos anchor fastener at 500 mm distance.**				
9.1	**100 x 75mm (With cover) for external refrigerant piping**	**0**	**RFT**		
9.2	**150 x 75mm (With cover) for external refrigerant piping**	**20**	**RFT**	**1410.07**	**28,201.40**
9.3	**300 x 75mm (With cover) for external refrigerant piping**	**0**	**RFT**		
9.4	**450 x 75mm (With cover) for external refrigerant piping**	**0**	**RFT**		
9.5	**600 x 75mm (With cover) for external refrigerant piping**	**0**	**RFT**		
9.6	**150 x 75mm (Without cover) for Internal refrigerant piping in exposed ceiling**	**0**	**RFT**		
9.7	**300 x 75mm (Without cover) for Internal refrigerant piping in exposed ceiling**	**0**	**RFT**		
9.8	**450 x 75mm (Without cover) for Internal refrigerant piping in exposed ceiling**	**0**	**RFT**		
10	**Control /communication wiring / Cabling for VRF System between Indoor and Outdoor units in PVC flexible conduit minimum 6kg/sq cm working pressure.**	**225.00**	**RFT**	**110.21**	**24,797.25**
11	**Supply and Fixing in position of UPVC condensate drain pipe with 6mm thick nitrile rubber insulation forr following sizes :**				
11.1	**ø80mm**	**0**	**RFT**		
11.2	**ø65mm**	**0**	**RFT**		
11.3	**ø50mm**	**0**	**RFT**		
11.4	**ø40mm**	**0**	**RFT**		
11.5	**ø32mm**	**0**	**RFT**		
11.6	**ø25mm**	**328.00**	**RFT**	**78.19**	**25,646.32**
11.7	**ø20mm** Signature and Stamp of Bidder	**295.20**	**RFT**	**65.95**	**19,468.44**

12	**One circuit of copper piping with insulation & control cabling complete with elbows, couplings etc for Dx type split AC units as per site requirement.**	**49.20**	**RFT**	**294.86**	**14,507.11**
13	**Supply, Testing and Commissioning of fabrication work & installation of M.S. work.(If required) etc complete as required by Client / Consultant / E-I-C. Pipes shall be of following sizes :**	**0**	**Kg**		
	PART-D AIR CONDITIONING WORKS TOTAL				**34,50,799.45**
PART-A + B + C + D TOTAL RS. 2,31,53,808.68					

(A) **Total Tendered Amount – Rs. 2,31,53,808.68**

(B) **Above/Below tender amount (if any) ……..…..……% in figure**

(……in Words)

(C) **Net Tendered Amount (A-B) = RS. ……..…..…**

(In Words :- Rupees ……..)

Signature of the Chief Executive Officer

Signature and Stamp of Bidder